

PACE-CONNELLY #6

CUT OFF AND PLATE
4' BELOW G.L.

LARAMIE-FOX HILLS
Bottom @ 319'

8 5/8 CASING
SET @ 558' -

SURFACE PLUG
0' - 100'
(41 SX)

SHOE PLUG
518' - 658'
(57 SX)

CUT & PULL
4 1/2 CASING
@ 3,000'

TOC @ 3047' -

STUB PLUG
2900' - 3050'
(45 SX)

2 SX ON BP
CIBP @ 4445'
SET ON 3/28/2013

Perfs
SUSSEX 4,495'
4,625'
SHANNON 4,930'
4,952'
PBTD 5,040' →