



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

TICKET NUMBER 44409  
LOCATION Chanute, KS  
FOREMAN Tussy

# FIELD TICKET & TREATMENT REPORT CEMENT

colo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																
10-26-13	6378	Hickman #1	21	13S	41W	Chanute																
CUSTOMER Pronghorn Operating			<table border="1"> <tr> <th>TRUCK #</th><th>DRIVER</th><th>TRUCK #</th><th>DRIVER</th></tr> <tr> <td>399</td><td>Damon M</td><td></td><td></td></tr> <tr> <td>52</td><td>Tim W</td><td></td><td></td></tr> <tr> <td></td><td>Mike R</td><td></td><td></td></tr> </table>				TRUCK #	DRIVER	TRUCK #	DRIVER	399	Damon M			52	Tim W				Mike R		
TRUCK #	DRIVER	TRUCK #					DRIVER															
399	Damon M																					
52	Tim W																					
	Mike R																					
MAILING ADDRESS																						
CITY	STATE	ZIP CODE																				

JOB TYPE surface HOLE SIZE 17 1/2 HOLE DEPTH 470' CASING SIZE & WEIGHT 13 3/8 48 #  
CASING DEPTH 470' DRILL PIPE TUBING OTHER  
SLURRY WEIGHT 14.8 SLURRY VOL 1.36 WATER gal/sk 6.5 CEMENT LEFT in CASING 30'  
DISPLACEMENT 69.1 DISPLACEMENT PSI MIX PSI RATE

REMARKS: Safety meeting on G-rail #3. Rig up and circulate, Mix 2.25 sacks  
Class 'A' 390cc 290cc. Drop plug and displace 69 BBLs and shut in  
cement did circulate approx 20 BBL to pit.

Thanks Tussy & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	1150.00	1150.00
5406	85	MILEAGE	5.25	446.25
5407A	20 Ton	Town Mileage Delivery	17.5	2975.00
11045	425 SACKS	Class 'A' cement	18.25	7883.75
1102	1199 #	Calcium Chloride	.94	1127.06
1118B	799 #	Bentonite	.27	215.73
4436	1	13 3/8 wood plug	179.25	179.25
		subtotal		13977.54
		less 1090		13977.54
		subtotal		12579.74
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION Joh Rin TITLE Company man DATE 10-28-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





## FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 44523  
LOCATION Duplex B.  
FOREMAN Norman Fuzzy

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY	
11/13/13	6378	Hanawa #1		21	13	44	Cheyenne	
CUSTOMER Pronahorn				Cheyenne wells 6 1/2 N E into				
MAILING ADDRESS					TRUCK #	DRIVER	TRUCK #	DRIVER
					463	Cory		
					528	Jermy S.		
CITY		STATE	ZIP CODE					

JOB TYPE <u>2 Port cullers</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2 15.5</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING _____	OTHER <u>PC 4422 + 2683</u>
SLURRY WEIGHT <u>14.2 / 12.5</u>	SLURRY VOL <u>142 / 1.88</u>	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>25.6 15.6</u>	DISPLACEMENT PSI <u>700 700</u>	MIX PSI _____	RATE _____

REMARKS: Softy Meeting Rig up on Coshell #2 Pressure up backside <sup>1000\*</sup> ~~Open~~ Tool pump to get a blow mix <sup>1000\*</sup> 5% cement Displace with 25 bbl water Pressure tool to 1000\* Trip in 4 Joints Reverse out with 50 bbl water Shut Down for 3 hrs. Pull up to Port Collar Pressure backside to 1000\* open tool pump to get a blow mix 250 SKs 60/60 mix = 8% Gel 1/4" PG 2% CC Displace with 15 bbl water Shut Tool pressure tool to 1000 Trip in 4 Joints Reverse out 30 bbl water Rig Down

[illegible]

Rayin 3737

AUTHORIZATION John H. [Signature] TITLE Company man DATE 11-13-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

TICKET NUMBER 44286  
LOCATION Orkley, KS  
FOREMAN Jerry V

# FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-4-13	6378	Hanavan #1	21	135	44w	Cherokee
CUSTOMER <u>Pronghorn</u>			Cheyenne Wells			
MAILING ADDRESS			6 miles N Einto			
CITY	STATE	ZIP CODE	TRUCK #	DRIVER	TRUCK #	DRIVER
			5302T118	Dane R		
			566	Cody R		
			assist	Dustin J		

JOB TYPE long string HOLE SIZE 7 7/8 HOLE DEPTH 5504 CASING SIZE & WEIGHT 5 1/2, 75.5  
CASING DEPTH 5502 DRILL PIPE  TUBING bottom P.C. top of 27' OTHER P.C. top of 68'  
SLURRY WEIGHT 12.5/14.2 SLURRY VOL 1.9 / 1.42 WATER gal/sk  CEMENT LEFT in CASING 11.93'  
DISPLACEMENT 130 1/2 bbl DISPLACEMENT PSI  MIX PSI  RATE

REMARKS: Safety meeting & rig up on Excell Rig 3, run float equip, turbolizers on 2, 3, 4, 5, 6, 27, 30, 109, 70, 71 centralizers on 1, 7, 8, 26, 28, 31, 67, 72, baskets on 27, 68. P.C. on top of 27' & 68' hook up to tree and pump ball thru w/ no circulation, hook up to pump truck & pump 5 bbl w/ flo-check w/ spacers and 5 bbl water after mix 5 SKS MH, 5 SKS RH, 65 SKS 60/40 mix gel 1/4" flo seal per sk and tail end 75 SKS DWC 5" Kol seal per sk shutdown & use plug wash pump & lines and displace with 130 1/2 bbl fresh water plug landed @ 1000 psi with 500# lift released & float hold press back up to 500# & shut in for 15 min. Never achieved circulation

Thank you Jerry & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54014	1	PUMP CHARGE	3400 <sup>00</sup>	3400 <sup>00</sup>
5406	85	MILEAGE	522	44370
5407A	6.7	ton mileage delivery	172	996.42
1126	75 SKS	DWC	2370	1777.50
1110A	375#	Kol seal	.56	210.00
1131	75 SKS	60/40 pro mix	15.86	1189.50
1118 B	516#	benonite gel	.27	139.32
1107	19#	flo seal	2.97	56.43
1102	200#	calicum chloride	.94	188.00
1111A	200#	metasilicate	2.52	504.00
4130	8	5 1/2 centralizers (w)	61.00	488.00
4136	10	5 1/2 Turbolizers (w)	75.75	757.50
4104	2	5 1/2 baskets (w)	290.00	580.00
4159	1	5 1/2 AFU float shoe (w)	433.75	433.75
4454	1	5 1/2 latel down assy (F)	318.25	318.25
4286	2	5 1/2 port collars (I)	2178.75	4357.50
1111	2	sodium chloride	N/C	N/C
		subtotal 15,842.62 less 10% disc. 1584.26	Subtotal	14,258.36
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION Josh Kleiser TITLE Company man DATE 11-4-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the custom account records, at our office, and conditions of service on the back of this form are in effect for services identified o