

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400491823

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

11/07/2013

Well Name: AP

Well Number: 322-20-695

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

Contact Name: Reed Haddock

Phone: (303)606-4086

Fax: (303)629-8268

Email: reed.haddock@wpxenergy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030107

WELL LOCATION INFORMATION

QtrQtr: NENW Sec: 20 Twp: 6S Rng: 95W Meridian: 6

Latitude: 39.517431

Longitude: -108.022931

Footage at Surface: 84 feet FNL/FSL FNL 2499 feet FEL/FWL FWL

Field Name: PARACHUTE

Field Number: 67350

Ground Elevation: 6909

County: GARFIELD

GPS Data:

Date of Measurement: 04/28/2010 PDOP Reading: 2.5 Instrument Operator's Name: Robert Kay

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL
1695 FNL 1295 FWL 1695 FNL 1295 FWL
Sec: 20 Twp: 6S Rng: 95W Sec: 20 Twp: 6S Rng: 95W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Lease map previously submitted.

Total Acres in Described Lease: 4588 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 1133 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 2101 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 5280 Feet

Above Ground Utility: 5280 Feet

Railroad: 5280 Feet

Property Line: 560 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 305 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 1295 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	440-31	320	

DRILLING PROGRAM

Proposed Total Measured Depth: 9372 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 305 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Spent drlg fluids are treated with a de-watering unit. Separated mud solids are disposed with the drill cuttings at a well pad location, or at an approved disposal trench. Separated water is re-used for drilling, or disposed at a permitted inj. well.

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	18	48	0	45	50	45	0
SURF	13+1/2	9+5/8	32.3	0	2609	664	2609	0
1ST	8+3/4	4+1/2	11.6	0	9372	828	9372	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL
This re-file contains changes in both the SHL, BHL, and TD. A new directional plan, plot, and survey plat are attached.
The current permit expires 2/23/2014.
I certify that there have been no changes on land use, lease description.
The pad has been built.
No pit will be used.
There will be no additional surface disturbance.
The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).
The location is not within a wildlife Restricted Surface Occupancy Area

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 335116

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Reed Haddock

Title: Regulatory Specialist Sta Date: 11/7/2013 Email: reed.haddock@wpenergy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 1/3/2014

Expiration Date: 01/02/2016

API NUMBER

05 045 21386 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED. SEE ATTACHED NOTICE.
- 2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS IS REQUIRED, WITH THE FOLLOWING EXCEPTION: ALL FIELD NOTICE REQUIREMENTS SPECIFIED IN THIS NOTICE TO OPERATORS ARE SUPERSEDED BY THE REQUIREMENTS OF THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY (SEE CONDITION OF APPROVAL #1). SEE ATTACHED NOTICE.
- 3) CEMENT ON PRODUCTION CASING MUST BE A MINIMUM OF 200' ABOVE THE TOP OF THE MESA VERDE FORMATION (OR 200' ABOVE THE OHIO CREEK FORMATION IF PRESENT). CEMENT TOP VERIFICATION BY CBL IS REQUIRED. THIS REQUIREMENT SHALL SUPERSEDE THE TOP OF CEMENT REQUIREMENTS IN THE MAMM CREEK FIELD NOTICE TO OPERATORS.

Best Management Practices

No BMP/COA Type	Description

Applicable Policies and Notices to Operators

Piceance Rulison Field - Notice to Operators.

NW Colorado Notification Policy.

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
400491823	FORM 2 SUBMITTED
400505383	Deviated Drilling Plan
400505384	WELL LOCATION PLAT
400505385	Directional Data

Total Attach: 4 Files

General Comments

User Group	Comment	Comment Date
Permit	Final review completed. No LGD comments.	12/31/2013 9:28:01 AM
Permit	Operator supplied refile statements.	12/31/2013 9:27:43 AM
LGD	pass, gdb	11/25/2013 2:22:47 PM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.	11/8/2013 4:33:40 PM
Permit	Passed completeness.	11/8/2013 8:30:38 AM

Total: 5 comment(s)