

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400533032

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Katie Kistner

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 9294317

3. Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-36886-00

6. County: WELD

7. Well Name: USA FED

Well Number: 02N-36HZ

8. Location: QtrQtr: SWSE Section: 36 Township: 3N Range: 66W Meridian: 6

Footage at surface: Distance: 611 feet Direction: FSL Distance: 1963 feet Direction: FEL

As Drilled Latitude: 40.176361 As Drilled Longitude: -104.722872

GPS Data:

Data of Measurement: 09/27/2013 PDOP Reading: 2.4 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 740 feet. Direction: FSL Dist.: 2398 feet. Direction: FEL

Sec: 36 Twp: 2N Rng: 66W

** If directional footage at Bottom Hole Dist.: 480 feet. Direction: FNL Dist.: 2393 feet. Direction: FEL

Sec: 36 Twp: 3N Rng: 66W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 09/19/2013 13. Date TD: 10/31/2013 14. Date Casing Set or D&A: 11/03/2013

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11764 TVD** 7257 17 Plug Back Total Depth MD 11737 TVD** 7256

18. Elevations GR 4996 KB 5009

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, GR, MUD

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	866	322	0	866	VISU
1ST	8+3/4	7	26	0	7,710	815	38	7,710	CBL
1ST LINER	6+1/8	4+1/2	11.6	6683	11,749				CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work: _____

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	7,211		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,343		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Katie KistnerTitle: Regulatory Analyst

Date: _____

Email: katie.kistner@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400535119	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400533089	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400533056	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400533071	PDF-GAMMA RAY	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400533073	PDF-GAMMA RAY	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400533074	LAS-GAMMA RAY	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400533075	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400533076	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400533078	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400533080	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User GroupCommentComment Date

--	--	--

Total: 0 comment(s)