

WELLBORE DIAGRAM

CURRENT WBD

990' FNL 990' FWL

Operator: Great Western Oil & Gas C

Well Name: Erica #1

Lease Number:

Location: NWNW, 34 T2N R66W

Field: Wattenberg J

County, State: Weld Co., CO

API Number: 05-123-09996

Diagram Date: 11/12/2013

Lat/Long

KB' 5005

GL' 5004

Spud Date: 7/17/1980

Date TD Reached: 7/28/1980

Completion Date: 1/5/1981

Producing Formation: J Sand

12 1/4" Hole
8 5/8" 20# set at 214'
200 sx Regular + 2.4% CaCl2

4-1/2" casing sleeve @ 791'
Anjel Fox Hills with 1,500 gal

7 7/8" Hole
4 1/2" 10.5# & 11.6# csg set at 8109'
Cmt'd w/250sx 50/50 POZ, 10% salt
20% silica flour, 2% gel
TOC @ 6810' (CBL)

2-3/8" Tubing

J Sand Perfs

7925-7931 = 7 holes, 0.4"

7943-7949 = 7 holes, 0.4"

7969 = 1 hole, 0.4"

7971 = 1 hole, 0.4"

750 gal 7-1/2 NE acid, 25,000 gal pre-pad,
25,000# 100 mesh, 476,000# 20/40 ss in
169,000 gal, w/60T CO2

PBTD = 8070'
TD = 8118'