

Shannon Hartnett

From: Diana Burn - DNR <diana.burn@state.co.us>
Sent: Tuesday, January 14, 2014 5:37 PM
To: Shannon Hartnett; Mike Hickey - DNR
Cc: Sarah Freeman - DNR; Jane Stanczyk - DNR
Subject: RE: Unplanned S/T - Tailholt FD 11-379HN APD 05-123-38582 UPDATED

Please proceed as proposed.

Diana

From: Shannon Hartnett [mailto:shartnett@gwogco.com]
Sent: Tuesday, January 14, 2014 3:32 PM
To: Burn - DNR, Diana (diana.burn@state.co.us)
Cc: Freeman, Sarah (sarah.freeman@state.co.us); Jane.Stanczyk@state.co.us; margaret.ash@state.co.us; randell.johnson@state.co.us
Subject: RE: Unplanned S/T - Tailholt FD 11-379HN APD 05-123-38582 UPDATED

Below is updated information...

i)

While running the 4-1/2" production liner it became stuck at 10,587' MD due to tight hole in that section of the wellbore.

ii)

Total measured depth – 11,906' MD / 7,117' TVD

iii)

Casing Details:

9-5/8" set at 1,036' MD/TVD

7" set at 7485' / 7159' MD/TVD

(Fish) 4-1/2" stuck from 5287' to 10587' MD

iv)

FISH DETAIL AND DEPTHS:

The 4-1/2" liner will be cut and pulled from a depth of +/-8100'.

Top of Fish at 8,100'

Bottom of fish at 10,587'

All casing left in the hole will be 4-1/2", 11.6#, P-110, LTC.

The following completion equipment will also be left in the hole:

Float Shoe: 10,587', Float Collar: 10,538', Landing Collar: 10,491', RSI Port: 10,488'

DIESEL SWELL PACKERS: 10431', 10244', 10057', 9869', 9635', 9408', 9175', 8941', 8708', 8476', 8254'

SLIDING SLEEVES: 10346', 10159', 9972', 9738', 9504', 9277', 9043', 8810', 8578', 8346', 8114'

v)

No cement plugs will be set. The 4-1/2" liner will be recovered from between +/-8,800' and +/-8,000' and an open hole sidetrack will be carried out.

vi)

No cement plugs will be placed.

vii)

Wellbore will be sidetracked to the Niobrara B zone which is the same zone as the original hole.

viii) directional plan attached.

Thank you,



Great Western
OIL & GAS COMPANY

Shannon Harnett

Regulatory Compliance Specialist
Great Western Operating Company, LLC
1801 Broadway, Suite 500
Denver, CO 80202
Direct: 303.398.0351
Cell: 303.525.3638
Fax: 866.522.1673

Privileged / Confidential information may be contained in this message. This information is intended solely for use by the individual entity named as the recipient. If you are not the intended recipient, be aware that any disclosure, copying, distribution, or use of the contents of this communication is prohibited. In such case, you should destroy this communication and notify the sender by reply email.