

WINS No.: 75083		KELLY 1A				Start Date: 9/3/2013		
AFE No.: 88438376		Operation Summary Report				End Date:		
Operator KERR-MCGEE OIL AND GAS ONSHORE LP		FIELD NAME WATTENBERG		SPUD DATE 12/8/79		GL 4,842	KB 4852	ROUTE S16
API 0512309848		STATE COLORADO		COUNTY WELD		DIVISION US ROCKIES REGION		
Lat./Long.: Lat./Long.: 40.15059 / -104.82243		Q-Q/Sect/Town/Range: NESW / 17 / 2N / 66W		Footages: 1,920.00' FSL 2,060.00' FWL				
MTD 8146	TVD 8146	LOG MD 4,638.00		PBMD 8114		PBTVD 8114		
DIRECTIONS: HWY 85 AND WCR 22-1/2, WEST 6/10 MILE, SOUTH INTO LOCATION.								
EVENT INFORMATION:		EVENT ACTIVITY: CONST- CAP WELL WORK		REASON: PREP TO BE P&A		AFE NO.: 88438376		
		OBJECTIVE: DEVELOPMENT		DATE WELL STARTED/RESUMED: 12/8/1979				
		OBJECTIVE2: HZ SAFETY PREP		EVENT END				
				STATUS:				
RIG OPERATIONS: Begin Mobilization Rig On Location Rig Charges Rig Operation Start Finish Drilling Rig Release Rig Off Location								
Date	Time Start-End	Duration (hr)	Phase	Code	Subco de	P/U	Operation	
11/8/2013	<u>SUPERVISOR:</u> JAY CHANDLER						<u>DWC:</u>	<u>CWC:</u> <u>MD:</u>
	9:00 - 10:00	1.00		30	A	P	MIRU ENSIGN 311	
	10:00 - 10:00	0.00		52	G	P	0 PSI, NO FLUIDS	
	10:00 - 11:30	1.50		46	F	P	WAIT ON OPERATOR TO REMOVE AUTOMATION.	
	11:30 - 12:00	0.50		30	E	P	BLOW WELL DOWN, CONTROL WELL W/ 40 BBLs.	
	12:00 - 13:00	1.00		30	F	P	NUBOP	
	13:00 - 17:30	4.50		31	I	P	LD 239 JTS OF 1-1/4" PRODUCTION TBG ON TRAILER.	
	17:30 - 18:00	0.50		30	G	P	CREW TRAVEL	
11/9/2013	<u>SUPERVISOR:</u> JAY CHANDLER						<u>DWC:</u>	<u>CWC:</u> <u>MD:</u>
	6:00 - 6:30	0.50		30	G	P	CREW TRAVEL	
	6:30 - 13:00	6.50		31	I	P	PU NC, SN AND 2-3/8" YELLOWBAND TBG TO 4000'	
	13:00 - 14:30	1.50		31	F	P	RU HALLIBURTON SERVICES. SPOT 3000# SAND PLUG ACROSS J-SAND PERFS.	
	14:30 - 16:00	1.50		31	I	P	TOOH W/ TBG	
	16:00 - 16:30	0.50		30	G	P	CREW TRAVEL	
11/9/2013	<u>SUPERVISOR:</u> JAY CHANDLER						<u>DWC:</u>	<u>CWC:</u> <u>MD:</u>
	13:14 - 14:30	1.27	WO/REP	35	E	P	GYRO SURVEY	
11/11/2013	<u>SUPERVISOR:</u> JAY CHANDLER						<u>DWC:</u>	<u>CWC:</u> <u>MD:</u>
	6:00 - 6:30	0.50		30	G	P	CREW TRAVEL	
	6:30 - 9:00	2.50		34	G	P	RU WARRIOR WIRELINE, RIH W/ 1-11/16" SINKER BAR AND TAG SAND PLUG IN LINER @ 7088'.	
	9:00 - 10:00	1.00		34	I	P	RIH AND SET CIBP @ 4370'. RD WIRELINE.	
	10:00 - 12:00	2.00		31	I	P	TIH W/ TBG TO CIBP	
	12:00 - 12:30	0.50		31	H	P	CIRCULATE GAS FROM WELL	
	12:30 - 13:00	0.50		33	C	P	TEST CSG TO 1500#, HELD GOOD	
	13:00 - 15:00	2.00		46	F	P	WAIT ON CEMENTERS	
	15:00 - 17:30	2.50		51	D	P	RU SANJEL CEMENTERS, SPOT 25 SX OF CLASS G CMT MIXED @ 15.8 PPG ON CIBP. DISPLACE W/ 14 BBLs H2O. PUH W/ TBG TO 3500'. CIRCULATE WELL CLEAN. SWI, SDFN	
	17:30 - 18:00	0.50		30	G	P	CREW TRAVEL	
11/12/2013	<u>SUPERVISOR:</u> JAY CHANDLER						<u>DWC:</u>	<u>CWC:</u> <u>MD:</u>
	6:00 - 6:30	0.50		30	G	P	`0630CREW TRAVEL	
	6:30 - 8:00	1.50		31	I	P	TIH AND TAG CMT PLUG @ 3842'. LD 3 JTS AND LAND WELL @ 3749.44" W/ 119 JTS	
	8:00 - 10:00	2.00		30	C	P	RDMO	