

## RE: Sidetrack Request - Razor 26K-2306B

Inbox x



Diana Burn - DNR

Jan 20 (2 days ago)

to Scott, Cole, me, Dirk, Jane

Please proceed as proposed.

**From:** Scott Webb [mailto:[ScottW@whiting.com](mailto:ScottW@whiting.com)]

**Sent:** Saturday, January 18, 2014 5:02 PM

**To:** [diana.burn@state.co.us](mailto:diana.burn@state.co.us)

**Cc:** Cole Orley

**Subject:** Sidetrack Request - Razor 26K-2306B

**RE: Sidetrack Request**

**RAZOR 26KI-2306B – API: 05-123-37878-00**

### **PROPOSED OR COMPLETED OPERATIONS:**

- **EXPLAIN THE SITUATION THAT HAS RESULTED IN THE NEED TO SIDETRACK:**

While pulling out of the horizontal portion of the hole, lost 27.16 feet of the BHL assembly consisting of the bit, bearing pack and rotor. Fish in hole at +- 8308' MD.

- **TOTAL DEPTH REACHED:**

- 11,434' (MD) 5705' (TVD)

- **CASING:**

- SURFACE CASING:

- SIZE: 9.625" 36PPF

- DEPTH: 1,503 MD 1500' TVD

- PRODUCTION CASING:

- SIZE: 7.0" 29 PPF J-55 LTC

- DEPTH: 6,142' MD 5,679' TVD

- **DESCRIPTION OF FISH IN THE HOLE:**

- 27.16 feet of the BHL assembly consisting of the bit, bearing pack and rotor

- **SIDETRACK PROCEDURE AND PLUG BACK DEPTHS:**

- No plug will be set in horizontal bore; Plan to trip in hole and push fish down to 9696'. Then pull back to 9470' MD and trough from 9470' to 9515'.redrilling around fish to permitted BHL Target.

- **SIDETRACK KICK OFF POINT:**

- 9515' (MD) 5701' (TVD)

- **BHL TARGET FOR SIDETRACK HOLE:**

- (SAME TARGET) 100' FNL AND 1815'FWL S23-T10N-R58W

- **VERBAL APPROVAL TO SIDETRACK:**

- Provided by Diana Burns 1/18/14.

**Scott Webb**  
Regulatory and Permitting Manager  
**Whiting Petroleum Corporation**  
*and its wholly owned subsidiary*  
**Whiting Oil and Gas Corporation**  
1700 Broadway, Suite 2300  
Denver, CO 80290  
Direct [\(303\) 390-4095](tel:(303)390-4095)  
Fax [\(303\) 390-4096](tel:(303)390-4096)  
[scottw@whiting.com](mailto:scottw@whiting.com)  
[www.whiting.com](http://www.whiting.com)

The information contained in this message may be privileged and confidential and protected from disclosure. If the reader of this message is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is strictly prohibited. If you have received this communication in error, please notify us immediately by replying to this message and deleting it from your computer.