

After P&amp;A Schematic:

8 5/8" 24# J-55 Surface  
Set @ 767' MD

Production TOC @ 1650'

4 1/2" 11.6# Production  
Set @ 7365' MD

PBTD: 7325'

Surface Plug  
12 sx at surface

Sting out of CICR  
5 sx cement on top CICR

Perf @ 825'  
CICR Set @ 725'  
Squeeze 150 sx cement

Sting out of CICR  
5 sx cement on top CICR

Perf @ 6990'  
CICR Set @ 6940'  
Squeeze 25 sx cement

## Perforation Data

Zone	Top (ft)	Bottom (ft)
Niobrara A	6990	6994
Niobrara A	6998	7000
Niobrara B	7054	7056
Niobrara B	7064	7070
Niobrara B	7126	7128
Niobrara C	7132	7136
Niobrara C	7152	7154
Codell	7240	7250