

After P&A Schematic:

8 5/8" 24# J-55 Surface
Set @ 759' MD

Production TOC @ 2938'

4 1/2" 11.6# Production
Set @ 7410' MD

PBTD: 7309'

Surface Plug
12 sx at surface

Sting out of CICR
5 sx cement on top CICR

Perf @ 825'
CICR Set @ 725'
Squeeze 150 sx cement

Sting out of CICR
5 sx cement on top CICR

Perf @ 7217'
CICR Set @ 7167'
Squeeze 25 sx cement

Zone Codell	Perforation Data	
	Top (ft)	Bottom (ft)
	7217	7236