



Project: RG 26-01S-098W

Site: RGU 11-26-198

Well: RGU 321-26-198

Design #2 05Nov13 kjs

T

M

Azimuths to True North
Magnetic North: 10.31°
Magnetic Field
Strength: 52229.0snT
Dip Angle: 65.98°
Date: 7/9/2013
Model: IGRF2010

ANNOTATIONS									
TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation	
120.00	120.00	0.00	0.00	0.00	0.00	0.00	0.00	Start Build 3.00	
326.26	326.67	6.20	93.39	-0.66	11.15	11.17	11.17	Hold 6.20 Inclination	
3500.00	3519.08	6.20	93.39	-21.05	355.33	355.95	355.95	Start Build 3.00	
4065.07	4106.42	23.82	93.39	-30.01	506.58	507.47	507.47	Hold 23.82 Inclination	
6370.00	6625.97	23.82	93.39	-90.22	1522.37	1525.04	1525.04	Start Drop -2.00	
7527.00	7816.99	0.00	0.00	-104.66	1765.97	1769.07	1769.07	Vertical	
7627.00	7916.99	0.00	0.00	-104.66	1765.97	1769.07	1769.07	Mesaverde	
12432.00	12721.99	0.00	0.00	-104.66	1765.97	1769.07	1769.07	TD at 12721.99	