

**KERR-MCGEE OIL AND GAS ONSHORE LP**  
**WHITEMORE 7-28A**  
**SW NE 28 2N 65W 2,161' FNL 1,930' FEL**  
**WELD,COLORADO**  
**02/04/2014**

AREA: E3      ROUTE: E36    Spud: 05/08/2003    WINS No.: 75374    AFE/WO#: 2094300    API#: 0512321425

GL: 4900    KB: 4812    MTD: 7820    TVD: 7820    LOG MD: 7823    PBMD: 7788    PBTVD: 7788

Directions:    WCR 41 & WCR 18, E1/2, S INTO.



<u>HOLE SECTIONS</u>	<u>Size</u>	<u>Top</u>	<u>Btm</u>	<u>TD Date</u>				
SURFACE	12.25	12	928	05/09/2003				
PRODUCTION	7.88	928	7820	05/12/2003				
<u>TUBULARS</u>	<u>Tool Type</u>	<u>Joints</u>	<u>Size</u>	<u>Weight</u>	<u>Grade</u>	<u>Thread</u>	<u>Top D</u>	<u>Bottom D</u>
SURFACE CASING	Casing	21	8.63	24	J-55	STC	12	915
PRODUCTION CASING	Casing	185	4.50	11.6	I-80	LTC	12	7788
		1	4.50				7788	7789
	Casing	1	4.50	11.6	I-80	LTC	7789	7817
	Casing Guide Shoe	1	4.50				7817	7818
PRODUCTION TUBING	Tubing	242	2.38	4.7	J-55	8RD EUE	12	7636
	Seating Nipple	1	2.38				7636	7637
	Notched Collar	1	2.38				7637	7638
BRIDGE PLUG	Cast Iron Bridge Plu	1	4.50				6860	6862
BRIDGE PLUG	CIBP With CMT Cap	1	4.50				7610	7612
CAST IRON CEMENT RETAINER	Cement Retainer	1	4.50				4272	4274
BRIDGE PLUG	Cast Iron Bridge Plu	1	8.63				160	163
<u>CEMENT JOBS</u>	<u>Stage</u>	<u>Sacks</u>	<u>Cement Jobs</u>	<u>Top D</u>	<u>Btm D</u>	<u>cbl</u>		
SURFACE CASING	STAGE 1	595	NEAT	12	915	No		
PRODUCTION CASING	STAGE 1	300	50/50 POZ-MIX	6350	7818	Yes		
PRODUCTION CASING	ABANDONMENT PLUC	35	LEAD FRESH WATER	6250	6860	No		
CAST IRON CEMENT RETAINER	ABANDONMENT PLUC	460	LEAD FRESH WATER	4050	5220	No		
SURFACE CASING	ABANDONMENT PLUC	250	LEAD FRESH WATER	650	1540	No		
<u>PERFORATIONS</u>	<u>Formation</u>	<u>Zone</u>	<u>Top</u>	<u>Btm</u>	<u>Date</u>	<u>Reason</u>	<u>Comments</u>	
			4200	4201	01/10/2014	CEMENT SQUEEZE		
			5220	5221	01/10/2014	CEMENT SQUEEZE		
J SAND			7673	7678	06/02/2003	PRODUCTION		
J SAND			7692	7694	06/02/2003	PRODUCTION		
J SAND			7700	7713	06/02/2003	PRODUCTION		

Comments: