



STATE OF
COLORADO

Weems - DNR, Mark <mark.weems@state.co.us>

PA Procedure for the Doerfer Wells

1 message

Weems - DNR, Mark <mark.weems@state.co.us>

Wed, Feb 5, 2014 at 11:07 AM

To: Beeman-Robert Beeman-Owner <robertbeeman@msn.com>

Cc: Steve Labowskie - DNR <steve.labowskie@state.co.us>, Mike Leonard - DNR <mike.leonard@state.co.us>,
Larry Coler - DNR <larry.coler@state.co.us>

**Beeman
Doerfer 1-5
API #05-083-06653**

Assuming the eform 5 you submitted is accurate, you could PA the well as follows:

- Cement plug to cover the perfs and tag after setting up or set a BP above and within 50' of the top perf w/ 2 sx cmt spotted on top (tagging not necessary for CIBP's).
- If the production casing pressure tests okay, then tagging cement plugs is not necessary.
- 100' cmt plug to straddle the same depth as the surface casing shoe (150'-250') .
- 15' surf cmt plug
- Cut casing off install PA marker c/w well ID

The following is missing and is needed to be attached to the eform 5

- The CBL run by Jet West
- The cement ticket depicting volumes used on the surface casing

An eform 5A - Completed Interval needs to be submitted

- The Jet West job ticket provided is dated 8/25/2009 and reports running a CBL and perforating from 1281' to 1286' (20 holes)

Additional production reports are required along with a sundry notice giving the well status and a summary of operations for each year since perforating the well since perforating the DK in AUG 2009.

- The production reports on file include only the years 2012 and 2013 and report zero production.

The inspection report dated 4/18/2012 reports:

- Oil stained dirt is found around the well head and the stock tanks.
- Inspection photos shows functional production equipment present & fully capable of producing the well.

I will not approve a form 6 - Notice of Intent to PA until all the above has been provided and approved.

Mark Weems, P. E.
Regional Engineer - SW Colorado

Colorado Oil and Gas Conservation Commission
50 Long Hollow Lane
Durango, CO 81301
(970) 259-4587 office
(970) 749-0624 cell