

FORM  
2

Rev  
08/13

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400330023

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

02/05/2014

Well Name: Chevron Well Number: GM 12-21  
Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC COGCC Operator Number: 96850  
Address: 1001 17TH STREET - SUITE #1200  
City: DENVER State: CO Zip: 80202  
Contact Name: Reed Haddock Phone: (303)606-4086 Fax: (303)629-8268  
Email: reed.haddock@wpxenergy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: \_\_\_\_\_

WELL LOCATION INFORMATION

QtrQtr: SENE Sec: 20 Twp: 6S Rng: 96w Meridian: 6  
Latitude: 39.511469 Longitude: -108.125508

Footage at Surface: 2034 feet FNL/FSL FNL 703 feet FEL/FWL FEL

Field Name: Grand Valley Field Number: 31290

Ground Elevation: 5574.9 County: GARFIELD

GPS Data:

Date of Measurement: 08/15/2012 PDOP Reading: 1.1 Instrument Operator's Name: Robert Kay

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1350 FNL 1001 FWL 1350 FNL 1001 FWL  
Bottom Hole: FNL/FSL 1350 FNL 1001 FWL  
Sec: 21 Twp: 6S Rng: 96W Sec: 21 Twp: 6S Rng: 96W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Lease is attached. Signed surface owner waiver letter attached.

Total Acres in Described Lease: 857 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC24099

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 193 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 604 Feet  
Building Unit: 626 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 227 Feet  
Above Ground Utility: 276 Feet  
Railroad: 5280 Feet  
Property Line: 1687 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).  
- Enter 5280 for distance greater than 1 mile.  
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.  
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 10/09/2013

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 303 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary \_\_\_\_\_ Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-13	0	640

## DRILLING PROGRAM

Proposed Total Measured Depth: 7332 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 303 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Spent drlg fluids are treated with a de-watering unit. Separated mud solids are disposed with the drill cuttings at a well pad location, or at an approved disposal trench. Separated water is re-used for drilling, or disposed at a permitted inj. well.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	18	48#	0	70	50	70	0
SURF	13+1/2	9+5/8	32.3#	0	1074	284	1074	0
1ST	8+3/4	4+1/2	11.6#	0	7332	772	7332	

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments Closed Loop. See WPX Master APD

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 335402

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Reed Haddock

Title: Regulatory Specialist Sta Date: 2/5/2014 Email: reed.haddock@wpxenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

API NUMBER

05

### Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type Description

--	--

### Best Management Practices

No BMP/COA Type Description

--	--

### Attachment Check List

Att Doc Num Name

400330023	FORM 2 SUBMITTED
400360201	DIRECTIONAL DATA
400360204	DEVIATED DRILLING PLAN
400392145	FED. DRILLING PERMIT
400541275	LEGAL/LEASE DESCRIPTION
400541278	ACCESS ROAD MAP
400541292	WELL LOCATION PLAT
400550432	WAIVERS

Total Attach: 8 Files

### General Comments

User Group Comment Comment Date

Permit	Returned to draft: Surface Use Agreement missing and needs to be attached for the right to construct.	2/6/2014 9:37:47 AM
--------	--	------------------------

Total: 1 comment(s)