

FORM  
2

Rev  
08/13

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400537545

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☐ MULTIPLE ZONES ☒ COMMINGLE ZONES ☒

Sidetrack ☐

Date Received:

Well Name: FEDERAL

Well Number: RGU 341-27-198

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: 1001 17TH STREET - SUITE #1200

City: DENVER

State: CO

Zip: 80202

Contact Name: ANGELA  
KRAISER

NEIFERT-

Phone: (303)606-4398

Fax: (303)629-8268

Email: ANGELA.NEIFERT-KRAISER@WPXENERGY.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: \_\_\_\_\_

WELL LOCATION INFORMATION

QtrQtr: LOT 4 Sec: 26 Twp: 1S Rng: 98W Meridian: 6

Latitude: 39.940159

Longitude: -108.368816

Footage at Surface: 639 feet FNL/FSL FNL 190 feet FEL/FWL FWL

Field Name: SULPHUR CREEK

Field Number: 80090

Ground Elevation: 6585

County: RIO BLANCO

GPS Data:

Date of Measurement: 02/14/2013 PDOP Reading: 2.7 Instrument Operator's Name: J KIRKPATRICK

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
677 FNL 539 FEL 677 FNL 539 FEL  
Sec: 27 Twp: 1S Rng: 98W Sec: 27 Twp: 1S Rng: 98W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T1S R98W

SEC. 21: NE/4NE/4, S/2NE/4, NE/4SW/4, S/2SW/4, SE/4

SEC. 22: LOTS 1 (38.84, NE/4NE/4), 2 (38.84, NW/4NE/4), 3 (38.57, NE/4NW/4), 4 (38.57, NW/4NW/4), 5 (38.66, SW/4NW/4), 6 (38.66, SE/4NW/4), 7 (38.86, SW/4NE/4), 8 (38.86, SE/4NE/4), 9 (38.84, NE/4SE/4), 10 (38.84, NW/4SE/4), 11 (38.72, NE/4SW/4), 12 (38.70, NW/4SW/4), 13 (38.78, SW/4SW/4), 14 (38.79, SE/4SW/4), 15 (38.84, SW/4SE/4), 16 (38.84, SE/4SE/4) [ALL]

SEC. 27: LOTS 1 (38.94, NE/4NE/4), 2 (38.90, NW/4NE/4), 3 (38.85, NE/4NW/4), 4 (38.82, NW/4NW/4), 5 (38.85, SW/4NW/4), 6 (38.88, SE/4NW/4), 7 (38.95, SW/4NE/4), 8 (38.99, SE/4NE/4), 9 (38.99, NE/4SE/4), 16 (39.02, SE/4SE/4) [N/2, E/2SE/4]

Total Acres in Described Lease: 1409 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC60731

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 539 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 2971 Feet

Building Unit: 2971 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 3416 Feet

Above Ground Utility: 727 Feet

Railroad: 5280 Feet

Property Line: 5280 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone ☐ Exception Zone ☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 321 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 5280 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): Ryan Gulch Unit Unit Number: 068239X

## SPACING & FORMATIONS COMMENTS

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK-ILES	WFILS			

## DRILLING PROGRAM

Proposed Total Measured Depth: 12270 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 321 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Spent drilling fluids are treated with a de-watering unit. Separated mud solids are disposed with the drill cuttings at a well pad location, or at an approved disposal trench. Separated water is re-used for drilling, or disposed at a permitted inj. well.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	18	48	0	80	50	80	0
SURF	14+3/4	9+5/8	36	0	3862	1402	3862	0
1ST	8+3/4	4+1/2	11.6	0	12270	1256	12270	7320

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: ANGELA NEIFERT-KRAISER

Title: REGULATORY SPECIALIST Date: \_\_\_\_\_ Email: ANGELA.NEIFERT-

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

API NUMBER

05

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--

## Best Management Practices

<b>No</b>	<b>BMP/COA Type</b>	<b>Description</b>
1	Planning	<ul style="list-style-type: none"> <li>* Share/consolidate corridors for pipeline ROWs to the maximum extent possible.</li> <li>* Minimize newly planned activities and operations within 300 feet of the ordinary high water mark of any reservoir, lake, wetland, or natural perennial or seasonally flowing stream or river.</li> <li>* Locate roads outside of drainages where possible and outside of riparian habitat.</li> <li>* Avoid constructing any road segment in the channel of an intermittent or perennial stream</li> <li>* Minimize the number, length, and footprint of oil and gas development roads</li> <li>* Use existing roads where possible</li> <li>* Combine utility infrastructure (gas, electric, and water) planning with roadway planning to avoid separate utility corridors</li> <li>* Where possible, consolidate pipeline and existing roadways, or roadways that are planned for development</li> <li>* Maximize the use of directional drilling to minimize habitat loss/fragmentation</li> <li>* Maximize use of remote completion/frac operations to minimize traffic</li> <li>* Maximize use of remote telemetry for well monitoring to minimize traffic.</li> </ul>
2	Drilling/Completion Operations	<ul style="list-style-type: none"> <li>* Use centralized hydraulic fracturing operations.</li> <li>* Install and maintain adequate measures to exclude all types of wildlife (e.g., big game, birds, and small rodents) from all fluid pits (e.g., fencing, netting, and other appropriate exclusion measures).</li> <li>* Conduct well completions with drilling operations to limit the number of rig moves and traffic.</li> </ul>
3	Interim Reclamation	<ul style="list-style-type: none"> <li>* Remove well pad and road surface materials that are incompatible with post-production land use and re-vegetation requirements</li> <li>* Use only certified weed-free native seed in seed mixes, except for non-native plants that benefit wildlife</li> <li>* WPX Energy will use certified, weed free grass hay, straw, hay or other mulch materials used for the reseeding and reclamation of disturbed areas.</li> <li>* Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents and openings.</li> <li>* Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors.</li> <li>* Avoid dust suppression activities within 300 feet of the ordinary high water mark of any reservoir, lake, wetland, or natural perennial or seasonally flowing stream or river where possible.</li> </ul>

Total: 3 comment(s)

## Attachment Check List

<b>Att Doc Num</b>	<b>Name</b>
400548336	DIRECTIONAL DATA
400548337	DEVIATED DRILLING PLAN
400548338	FED. DRILLING PERMIT
400548339	WELL LOCATION PLAT
400548340	ACCESS ROAD MAP

Total Attach: 5 Files

## General Comments

<b>User Group</b>	<b>Comment</b>	<b>Comment Date</b>

Total: 0 comment(s)