

US ROCKIES REGION

Anadarko Daily Summary Report

Well: SHAFER USX W 35-7

Project:COLORADO-WELD-NAD83-UTM13

Site:SHAFER USX W 35-7

Rig Name No:CONCORD 5/5

Event: CONST- CAP WELL WORK

Start Date: 11/27/2013

End Date:

Spud Date: 6/8/1983

Active Datum: RKB @5,111.00usft (above Mean Sea Level)

UWI: SHAFER USX W 35-7

| Report No | Report Date | MD (usft) | 24 Hr Summary |
|-----------|-------------|-----------|--|
| 1 | 12/10/2013 | | MIRU Slickline,RIH Remove production EQP,POOH,RIH TAG FILL,POOH,RDMO. |
| 2 | 12/13/2013 | | MIRU Service Rig & EQP,Control well, ND WH, NU BOPs, MIRU EMI EQP, TOOHD LD BAD TBG. |
| 3 | 12/16/2013 | | CT,SM,PU RBP TIH SET W/228 JTS @7269',C&CH clean,Spot sand,Test RBP to 1000psi,TOOH. |
| 4 | 12/17/2013 | | CT,SM,Isolate top and bottom of CSG leak,TOOH, ND BOPs,ND WH,ND Scsg head, Install new Scsg head,Install 5000psi WH,NU BOPs.SDFN,CT. |
| 5 | 12/18/2013 | | PU RH, TIH W/ 228JTS , C&CH Clean, Release RBP TOOHD.MIRU Wireline TIH W/ CIBP set @7952' DB 2 SX CM, Set 2nd CIBP @7280',RDMO WL. |
| 6 | 12/19/2013 | | CT,SM,Work on stuck RBP C&CH,MIRU WL, Run free point,POOH,RIH W/ Cutter, Cut TBG @3760'.LD 1 JT, SDFN CT. |
| 7 | 12/20/2013 | | TOOH W/ 116 JTS & 10 Cut JT,PU Over shot,Bumper sub,Jars,4xDriller collars,Energizer, 115 JTS 2-3/8" J-55,Latch on and Jar on RBP. |
| 8 | 12/21/2013 | | CT,SM, JAR on RBP,SDFN, CT. |
| 9 | 12/23/2013 | | CT,SM,Release off of fish TOOHD, Stand back collars, PU Burn shoe and Washover pipe and Jars, TIH Tag up break circulation Mill on RBP.SDFN,CT. |
| 10 | 12/24/2013 | | CT,SM,Swivel up 1 JT C&CH Drill on RBP, SDFN, CT. |
| 11 | 12/26/2013 | | CT,SM,RIH W/ 37 JTS Tag up,Rig up Swivel,Drill on RBP W/ Burn Shoe, TOOHD W/ TBG, LD Tools.SDFN,CT. |
| 12 | 12/27/2013 | | CT,SM,PU Fishing Tools TIH Latch on and Jar on RBP. |
| 13 | 12/28/2013 | | CT,SM,PU Tapered Mill & TIH W/ TBG Tag up & RU Power Swivel Mill on BAD CSG Between 3778'-3794'. |
| 14 | 12/30/2013 | | CT,SM,PU Burn Shoe & Wash over pipe & Jars, TIH W/ TBG Tag up on RBP & Mill on RBP.TOOHD & SDFN, Drain P&T Lines, CT. |
| 15 | 12/31/2013 | | CT,SM,PU Burn Shoe & Wash Over Pipe, TIH Tag Up On RBP & RU Power Swivel & Mill On RBP, TOOHD, SDFN, Drain P&T Lines, CT. |
| 16 | 01/02/2014 | | CT, SM, Ru Fishing Tools, TIH W/ TBG , Tag Fish & Jar on RBP/ Could not latch on, TOOHD,TIH W/ TBG Tag Fish & TOOHD & RIH W/ Mill & Dress Up TBG Fish,TOOH, SDFN,CT. |
| 17 | 01/03/2014 | | CT,SM, TIH Drill Collars & LD Drill Collars, TIH W/ TBG To 3860' , MIRU WireLine & Run Gyro On Well Bore, RDMO WireLine, LD TBG On Trailer, Prep Well For Cement Job. |
| 18 | 01/04/2014 | | CT,SM,TIH W/ TBG Tag Up & Set TBG For Cement, & MIRU SANJEL 3 Stage Cement W/ 195 SX Class "G" Cement, & RD Cement Crew,SDFN, CT. |
| 19 | 01/06/2014 | | CT,SM, Warm Up EQP, TIH & Tag Cement Top, LD TBG, TIH W/ 73 JTS , SDFN,CT |
| 20 | 01/07/2014 | | CT,SM,TIH Set TBG Above CMT Top, Pump 26bbl 9lb Mud, TOOHD LD 36 JTS & Stand Back 19 Stands,MIRU Wireline & Jet Cut CSG @ 920' RDMO WL,ND,NU,LD CSG On Trailer, SDFN,CT. |
| 21 | 01/08/2014 | | CT,SM,ND WH, NU Flang, NU BOPs, RU Laydown Line & LD CSG On Trailer,TIH W/2-3/8" TBG=39JTS=1238',MIRU CMT EQP,Pump 125 SX Type 3 CMT From 1238'-570',TOOH W/TBG RC POOH,RDMO CMT EQP, |
| 22 | 01/09/2014 | | CT,SM,TIH Tag Up Spot 33 bbl of 9 lb Mud,LD TBG, MIRU WireLine, Set CIBP @ 100', RDMO WireLine,RDMO Work Over Unit. |
| 23 | 01/10/2014 | | MIRU WireLine,RIH Set 9-5/8" CIBP @ 96',POOH,RDMO WireLine. |
| 24 | 02/03/2014 | | Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 95'. Filled casing stub with 43 bags 5000# cement. Capped casing with metal plate containing well info. Backfilled. |