





Continental Industries Field Services, LLC
 2411 N. Oil Drive
 P.O. Box 656
 Casper, WY 82602

307-473-1581 Phone
 307-234-1035 Fax

www.wellplugging.com

DAILY WORK TICKET

Company: Chesapeake Operating INC.
Address: P.O. Box 18496
Oklahoma City, OK. 73154
AFE # 802955 **Prop #** 636676

Date: 1/16/2014 **Rig:** CTU
Lease: Wildcat
Well: State 16-9-66 1H
County: Weld

PLUGGING / WORK DETAIL:

Conduct safety meeting, RU CTU, RU cementers, and water trucks, RIH and tagged TOC @ 1141', consult with Chesapeake rep, POOH to 470', establish circulation, mixed and pumped 180sxs cement to surface, 180sxs=36bbls slurry, 3.5bbls flush, rate was 1.5bpm @ 700psi, POOH, WOC. Approval was given by COGCC, to mix cement from 2nd plug to surface.

ITEM	HOURS OR UNITS	PRICE PER HOUR	TOTAL
------	----------------------	----------------------	-------

BID PRICE			\$ -
-----------	--	--	------

ADD'L TIME & MATR'L ITEMS:

Additional cement	160		\$
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
SUB TOTAL:		\$	
SALES TAX:		\$	
TOTAL:		\$	

EMPLOYEE'S NAME	JOB	HOURS
-----------------	-----	-------

LeMay	Supervisor	
Campbell	Operator	
Poisson	Derrick	
Kneel	Floor	
LeMay	CMTR	
Henson	BULK	
Russell E. Henson Jr.	CO REP	

CEMENT DETAIL

Cement pumped was class G Neat with slurry weight of 15.8 ppg, 1.15 cu-ft/sk yield. Mix water was 4.96 gal/sk. Compressive strength 24 hrs/4000 psi

PREPARED BY: RL

