

## After Replug Schematic:

36" Conductor Pipe  
Set @ 20'

7" Intermediate  
Set @ 203' MD

10 3/4" Surface  
Set @ 204' MD

7 7/8" OH  
To 6885' MD

~50' cement @ top of all casing strings

205 sx cement circulated to surface of  
Intermediate Csg

50 sx balanced plug from 344' to 175'

90 sx balanced plug from 2995' to 2689'

