

Magna Energy Services, LLC
17509 County Road 14
Ft. Morgan, CO 80701
(970) 867-9007
Fax (970) 867-8374

Job Log

Date: 1/21/13

Operator: Noble Energy

Well Name: Spike State GWS D 10-16

Legal Location: SESE Sec 10 T3N R64W
API # 05-123-15927-00

1/16/14: MIRU P&A equipment

1/17/14: Check PSI, Tbg 150#'s, Csg 150 #'s, Blow well down, Circulate well bore w/ 80 bbls water, ND well head, NU B.O.P.'s, LD 1.9" Tbg (recovered 207 jts @ 6904'), RU Magna WL, RIH w/ JBGR @ 6900', ROH, RIH w/ CIBP set @ 6879', ROH, RIH w/CDB w/ 2 sxs of cement on top of CIBP @ 6879', ROH, RD Magna WL, SWI.

1/18/14: Gyro well

1/20/14: RU JW WL, RIH w/ CIBP set @ 4263', ROH, RIH w/ CDB w/ 2sxs of cement on top of CIBP @ 4263', ROH, RD JW WL, ND B.O.P.'s, unland csg, NU B.O.P.'s, RU Magna WL, RIH w/ jet cutter, Cut csg @ 2500', ROH, RD Magna WL, LD csg (recovered 81 jts of 3.5" csg @ 2500'), PU tbg @ 2517', establish circulation w/ 10 bbls water, Mix & pump 100 sxs of 15.8# Class G cement @ 2517', Displaced w/ 10 bbls water, LD tbg, SWI.

1/21/14: PU tbg @ 586', establish circulation w/ 5 bbls water, Mix & pump 270 sxs of 15.8# Class G Cement to surface, LD tbg, RD P&A equipment, Top off well w/ 40 sxs of 15.8# Class G Cement, Dig up well & flow line 8' below ground surface, Cut & cap well & flow line 6' below ground surface, Backfill, P&A complete.

*** All cement used is Class "G" Neat 15.8 # ***

Cementing Contractor: Magna Energy Services, LLC
Cementing Contractor Supervisor: Scott Marez
Operator Supervisor: Kelly Reinhardt
COGCC Representative: Randell Johnson
Wireline Contractor: JW Wireline Co., Magna Energy Services, LLC

FIELD TICKET

Address: _____ State CO

Company Rep. Erich Zwagstra Date 1/21/14 Job Complete YES / NO

[illegible]