

## McPhearson #2

660' FNL1980 FEL NWNE 19 5N 61W 6th PM  
Lat 40.391987 Long -104.249875 (from footages)  
Weld County, Colorado  
API #05-123-05180

Spud date 10/26/1956

4568' KB  
4559' GL

5 sx surface plug

Water No Fox Hills  
(Within 1 mile radius)

Heavy mud

10.75", Wt, Grade, 89', 12.25" hole  
Cemented to surface w/ 150 sx.

10 sx shoe plug

Plugging summary  
TD(6709), Sand(TD-6662), 5sx cmt(6662-6631),  
pulled csg(5800-0), mud(6631-89),  
10 sx cmt shoe plug(89-53),  
mud(53-18), 5 sx cmt surf plug

As found in well:  
W Riverside 20-1, API 05-123-22285

Parkman 3197

TOC 5739 '

Niobrara 6086 '

Carlisle 6258 '

D Sand 6638 '

J Sand 6700 '

5 1/2", 15 1/2#, Grade, 6735', 7 7/8" hole  
Cemented with 150 sx

PBTD 6735 ft  
TD 6744 ft 7/7/1956

Updated 1/29/2014 srw