



## FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 44593

LOCATION Ozkiety KS

FOREMAN Dene R. Jerry Y

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
1-10-14	5659	APC-Betty 1-27	27	16s	45W	Cheyenne
CUSTOMER			<div> <div>Cheyenne Wells Rd RDC.</div> <div>West to Deadend</div> <div>3/4 south</div> <div>West into</div> </div>			
Mull Drilling						
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Steve D.		
CITY			566	Lance E		
STATE						
ZIP CODE						

JOB TYPE <u>Surface</u>	HOLE SIZE <u>13 1/4</u>	HOLE DEPTH <u>343</u>	CASING SIZE & WEIGHT <u>8 5/8 24 LBS</u>
CASING DEPTH <u>343</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT _____	SLURRY VOL <u>1.36</u>	WATER gal/sk _____	CEMENT LEFT in CASING <u>20'</u>
DISPLACEMENT <u>20.5</u>	DISPLACEMENT PSI <u>430</u>	MIX PSI _____	RATE _____

REMARKS: Safety meeting on Margin 20 Rig up and circulate, mix 275 sks  
Class A 3% cc, 2% gel. Displace with 250 BBL of water. Shut in cement did  
circulate. Circulated 6 bbls to pits

[illegible]

Ravin 3737

## AUTHORIZATION

**TITLE**

DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



**CONSOLIDATED**  
Oil Well Services, LLC

265619

TICKET NUMBER 38189  
LOCATION Oakley KS  
FOREMAN Miles Shaw

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
1-24-14	5659	APC Betty #1-27	27	16S	4SW	Cherokee
CUSTOMER <u>Mull Drilling</u>			TRUCK #			
MAILING ADDRESS			DRIVER			
CITY			TRUCK #			
STATE			DRIVER			
ZIP CODE			TRUCK #			
			DRIVER			

JOB TYPE 25' log HOLE SIZE 7 7/8" HOLE DEPTH 5490 CASING SIZE & WEIGHT 5 1/2" 15.5 #  
CASING DEPTH 5492 DRILL PIPE TUBING OTHER Duked @ 27.58  
SLURRY WEIGHT 14.2/107 SLURRY VOL 1.44/2.9 WATER gal/sk CEMENT LEFT IN CASING 42.00 #  
DISPLACEMENT 130 1/2/6746 DISPLACEMENT PSI 80/50 MIX PSI 1400/1500 RATE

REMARKS: Safety Meeting and rig up on Martin drilling rig #20 Flat equipment  
Turbolizers on Snts # 2, 4, 6, 8, 10, 12, 14, 16, 18, 20, 22, 24, 26, 28, Centralizers on Snts 64 & 66  
Basket son Snts # 2 & 65 Duked top of 65 @ 27.58' Run casing to bottom Circulate casing  
2 hrs pump Flo check mix 225 sls OWC with 5 # 403 ml down casing Shut down  
Clear pump & lines Release plug displacer 60 bbls water 70% bbls mud with 800-1/1  
plug landed & held @ 1400 psi. Dropped opening dart @ 800 psi; establish circulation Circulate  
Casing 3 hrs pump 5 bbls water mix 380-545 C.M.D down casing Shut down Clear  
Pump & lines displacer 67 bbls water with seeps; lift pressure plug landed & held @  
1500 psi. Cement did circulate 25 bbls top it  
Mix 105 sls RH 10 sls m #

Thanks Miles & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	3400.00	3400.00
5406	85	MILEAGE	5.25	446.25
5407A	29.4 tons	Ton Mileage delivery	1.75	4373.25
1144C	500 gal	Flo check	1.48	740.00
1104D	400 sls	C.M.D	27.92	11168.00
1107	100 #	Flo seal	2.97	297.00
1110A	1125 #	Kol seal	.56	630.00
1111	200 #	Salt	10/12	11/12
1126	225 sls	OWC	23.70	5332.50
4104	2	5 1/2" Baskets	290.00	580.00
4130	2	5 1/2" Centralizers	61.00	122.00
4136	14	5 1/2" Turbulizers	75.75	1060.50
4159	1	5 1/2" A/S shoe	433.75	433.75
4277A	1	5 1/2" Ducktail W	4900.00	4900.00
4454	1	5 1/2" Latch down plug	567.00	567.00
		Subtotal		34050.25
		10% discount		3405.03
		Subtotal		30645.22
		SALES TAX 7.165		1778.45
		ESTIMATED TOTAL		32423.67



completed

Ravin 3737

AUTHORIZATION

Miles Shaw

TITLE

Prod. Foreman

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.