



Exploration and Production

Well P&A Procedure


Wasatch Top:
Surface

8-5/8" Csg: 296'
Hole size: 12.25"

TOC -783'

Hole in 4-1/2" Csg
773', repaired with
200 sx cmt

CIBP-1365', + 2
sks cmt



Well Name **TW 8-36**
Location **36-T6S-R96W**
Field **Grand Valley**
County **Garfield, CO**
API **05-045-06707**
KB 5485 ft
Footages 1509 FSL 689 FWL

Spud 10/19/1994

Casing	296'	8-5/8" 24#
Cement	200 sx	
Casing	2024'	4-1/2" 11.6#
Cement	375 sx	

Tubing **N/A**

Formation Tops

Wasatch Surface

TOC - Bond Log 783'

Completed Intervals

	<u>Depth</u>	<u># Holes</u>
<u>Wasatch</u>	1398'-1540'	34
<u>Wasatch</u>	1856'-1894'	27

Cement Squeezes

<u>Depth</u>	<u># Holes</u>	<u>Sx</u>
773'	1	200

TD **2024', 4-1/2" Csg, Hole Size, 7-7/8"**