

# WELLBORE DIAGRAM

2/26/2014

ACTUAL

JRR

Mineral Resources, Inc

Driftwood #D1

NENE 20, T5N R65W  
40.39132, -104.68193

Weld County, CO  
05-123-24197

Notes:

G.L.= 4675

DEVIATED WELLBORE

K.B.= 4691

Vert Sec: 2038'

16

Max Angle: 30

8-5/8", Surf. CSG @ 676' (12-1/4" Hole)

Cmt'd w/ 480 sx

230 jnts 2-3/8" TBG Set @ 7463'

TOC=2,350'

NBRR-7220'

CODL-7474'

**CODL** Re-Perf'd **7476'-7486'** 4SPF, 0.42" 03/30/11 **PR**

Perf'd 7476'-7486' 4SPF, 0.42" 01/25/07

Re-Frac'd 04/02/11 ISIP=2605, ISDP=3970, ATP=5719, ATR=51.9

w/ 129,570 gal fluid and 252,300# 20/40 sand (31,836 gal SW, 97,734 gal xlink gel)

Frac'd 2/1/07 & 2/15/2007 ISIP=3740,

w/ 144,773 GAL FLUID, 140,263# 20/40 SAND

Cleaned out to 7507' (04/20/11)

PDTD= 7582

4-1/2" 13.5# CSG set @ 7620' (7-7/8" Hole)

PBTVD= 7182

Cmt'd w/ 620 sx

TD= 7620

TVD= 7220

\* all measurements from KB (MD) unless otherwise indicated