

Magna Energy Services, LLC
17509 County Road 14
Ft. Morgan, CO 80701
(970) 867-9007
Fax (970) 867-8374

Job Log

Date: 2/19/14
Operator: Noble Energy
Well Name: Martinson 25-06F
AFE # 142966 Weld County
Legal Location: SENW SEC 25 T4N R66W
API # 05-123-14947

2/14/14: MIRU, P & A equipment, Check PSI 200 #' on tbq. 200 #' on csg. Blow well down, pump 60 bbls water to kill well. ND well head ,NU B.O.P.S. TOO H w/ tbq., RU JW WL, RIH w/ CIBP @ 6890' ROH RIH W/ CDB dump 2 sxs of 15.8 # class G cement on top of CIBP @ 6890' ROH RD JW WL.TIH w/ tbq. @ 4340" SWI..


2/17/14: Check psi 0 #'s establish circulation @ 4340' mix & pump 15 sxs of 15.8 # class G cement, TOO H w/ tbq. Ru Magna WL RIH w/ csg. Cutter cut 4 ½ csg. @ 2504' ROH, RD Magna WL.LD 4 ½ csg.
(recovered 2504' of 4 ½ csg. 61 jts.) SWI.

2/18/14: Check psi 0 #' s TIH w/ tbq. @ 2504' establish circulation mix & pump 100 sxs of 15.8 # class G cement, TOO H w/ tbq.(Wait on tag). TIH w/ tbq. Tag. Cement @ 2250' TOO H w/ tbq. @ 660' establish circulation mix & pump 250 sxs of 15.8 # class G cement to surface. TOO H w/ tbq. Flush flow line w/ 4 bbls water, 1 bbl cement. SWI.

2/19/14:Check psi 0 #s TIH w/ tbq. tag TOC cement @ 125" establish circulation mix & pump 40 sxs of 15.8 # class G cement to surface, RD P&A equipment, MO, ' dig well & flow line 6' below ground level cut and cap well & flow line 6' below ground level backfill, PU location, P&A complete.

*** All cement used is Class "G" Neat 15.8 # ***

Cementing Contractor: Magna Energy Services, LLC
Cementing Contractor Supervisor: Jose Mario Navarro
Operator Supervisor: Kelly Reinhardt
COGCC Representative: John Montoya
WL contractor Magna WL Energy Services, JW WL. Services.

Company:	MAGNA ENERGY SERVICES LLC			 JW WIRELINE COMPANY 1-877-457-0013 wireline@jwenergy.com http://www.jwenergy.com/jw-wireline-company	Date:	02/14/2014
Address:	17509 COUNTY RD 14 FORT MORGAN, CO 80701-8904				SO No:	07-19-015672-0097
Well Name:	MARTINSON 25-06F				District:	Sterling, CO
Field Name:	WATTENBERG				Truck No:	A-2829
Well County:	WELD				Crane:	
Well State:	CO				Crew:	Dan Borgman - OPERATOR 1 James Smith - OPERATOR 2 Lucas Unrein - OPERATOR 1
Customer #:		PO #:	5435			
Contract #:		AFE #:				
Property #:						

JOB DATA					
Casing Size/Weight: /	TD of Casing:	From (depth) ft:	To (depth) ft:		
Tubing Size/Weight: /	TD of Tubing:	From (depth) ft:	To (depth) ft:		
Well Deviation:	Fluid Level:	Fluid Type:	Fluid Density:	Fluid Salinity:	
BH Pressure:	WH Pressure:	BH Temp:			
Section/Township/Range:	Lat/Long: /	X/Y Coordinates: /			
Log Measured from:	Log Interval:				
Arrival Time @ 2/14/2014 11:30 AM	Departure Time @ 2/14/2014 2:00 PM	Total Job Time: 02:30			
Well to JW @ 2/14/2014 10:00 AM	Well to Customer @ 2/14/2014 1:00 PM	Total Operating Time: 03:00			

SERVICE ORDER DETAILS							
Item #	Service Code	Description	Qty/Depth	Unit Price	Per	Line Total	Cust. Price
1	WLE8-0009	Wellsite Setup Charge	6000		Per Foot		
2	WLE8-0018	Environmental Fee	1		Per Job		
3	WLE6-0008	Cast Iron Bridge Plug (2" - 5 1/2")	1		Per Each		
4	WLE4-0010	Dump Bail General Depth Charge	6890		Per Foot		
5	WLE4-0011	Dump Bail General Operations Charge	1		Per Run		
6	WLE6-0001	Bridge Plug Setting Depth Charge	6890		Per Foot		
7	WLE6-0002	Bridge Plug Setting Operation Charge	1		Per Run		

SET PLUG @ 6890', TWO SACKS OF CEMENT

Total Discountable Items:

Discount:

Discountable SubTotal:

Total Non-Discountable Items:

Sales Tax: (0.00 %)

Grand Total:

The undersigned ("Company") agrees to pay J-W Wireline Company ("Contractor") for the operations to be conducted, or personnel or equipment listed above ("Services") at P.O. Box 226406, Dallas, Texas 75222-6406. The Services shall only be provided according to the Contractor's general terms and conditions ("Terms") as contained in part on the other side of this Purchase Order and as more fully set forth at www.jwenergy.com/pages/wireline-terms and upon request. THESE TERMS CONTAIN PROVISIONS RELATING TO INDEMNITY, RELEASE OF LIABILITY, LIMITATION OF WARRANTY AND ALLOCATION OF RISK.

Print Name	Signature	Date
------------	-----------	------