

FORM
2A

Rev
08/13

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400540713

Date Received:

03/11/2014

Oil and Gas Location Assessment

☐ New Location ☐ Refile ☒ Amend Existing Location Location#: 427635

Submit signed original form. This Oil and Gas Location Assessment is to be submitted to the COGCC for approval prior to any ground disturbance activity associated with oil and gas operations. Approval of this Oil and Gas Location Assessment will allow for the construction of the below specified Location; however, it does not supersede any land use rules applied by the local land use authority. Please see the COGCC website at <http://cogcc.state.co.us/> for all accompanying information pertinent this Oil and Gas Location Assessment.

Location ID:

427635

Expiration Date:

☒ This location assessment is included as part of a permit application.

CONSULTATION

- ☐ This location is included in a Comprehensive Drilling Plan. CDP # _____
- ☐ This location is in a sensitive wildlife habitat area.
- ☐ This location is in a wildlife restricted surface occupancy area.
- ☐ This location includes a Rule 306.d.(1)A.ii. variance request.

Operator

Operator Number: 100185
Name: ENCANA OIL & GAS (USA) INC
Address: 370 17TH ST STE 1700
City: DENVER State: CO Zip: 80202-5632

Contact Information

Name: Chris McRickard
Phone: (720) 876-5586
Fax: (720) 876-6584
email: chris.mcrickard@encana.com

RECLAMATION FINANCIAL ASSURANCE

☒ Plugging and Abandonment Bond Surety ID: 20100017 ☐ Gas Facility Surety ID: _____
☐ Waste Management Surety ID: _____

LOCATION IDENTIFICATION

Name: Minch Number: 4H-L368
County: WELD
QuarterQuarter: NWSW Section: 4 Township: 3N Range: 68W Meridian: 6 Ground Elevation: 5077
Define a single point as a location reference for the facility location. When the location is to be used as a well site then the point shall be a well location.
Footage at surface: 1677 feet FSL from North or South section line
453 feet FWL from East or West section line
Latitude: 40.252250 Longitude: -105.016080
PDOP Reading: 1.6 Date of Measurement: 01/16/2013
Instrument Operator's Name: John Rice

RELATED REMOTE LOCATIONS

(Enter as many Related Locations as necessary. Enter the Form 2A document # only if there is no established COGCC Location ID#)

This proposed Oil and Gas Location is:

LOCATION ID #

FORM 2A DOC #

FACILITIES

Indicate the number of each type of oil and gas facility planned on location

Wells	10	Oil Tanks		Condensate Tanks	18	Water Tanks	4	Buried Produced Water Vaults	
Drilling Pits		Production Pits		Special Purpose Pits		Multi-Well Pits		Temporary Large Volume Above Ground Tanks	
Pump Jacks		Separators	8	Injection Pumps		Cavity Pumps			
Gas or Diesel Motors		Electric Motors		Electric Generators		Fuel Tanks		Gas Compressors	
Dehydrator Units		Vapor Recovery Unit	8	VOC Combustor	12	Flare		LACT Unit	
								Pigging Station	1

OTHER FACILITIES

Other Facility Type

Number

Gas Buffer Vessels	1
Vapor Recovery Towers	1

Per Rule 303.b.(3)C, description of all oil, gas, and/or water pipelines:

Produced gas will be connected to gathering lines. Oil will be stored on site in tanks.

CONSTRUCTION

Date planned to commence construction: 03/01/2015 Size of disturbed area during construction in acres: 8.00
Estimated date that interim reclamation will begin: 03/01/2016 Size of location after interim reclamation in acres: 3.00
Estimated post-construction ground elevation: 5077

DRILLING PROGRAM

Will a closed loop system be used for drilling fluids: Yes

Is H₂S anticipated? No

Will salt sections be encountered during drilling: No

Will salt based mud (>15,000 ppm Cl) be used? No

Will oil based drilling fluids be used? No

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Method: Land application

Cutting Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: or Document Number:

Centralized E&P Waste Management Facility ID, if applicable:

SURFACE & MINERALS & RIGHT TO CONSTRUCT

Name: Don & Betty Minch

Phone: 970-535-4233

Address: 17076 Weld County Road 5

Fax: _____

Address: _____

Email: _____

City: Berthoud State: CO Zip: 80513

Surface Owner: ☒ Fee ☐ State ☐ Federal ☐ Indian

Check all that apply. The Surface Owner: ☒ is the mineral owner

☒ is committed to an oil and Gas Lease

☒ has signed the Oil and Gas Lease

☐ is the applicant

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed from or produced to this Oil and Gas Location: Yes

The right to construct this Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

Date of Rule 306 surface owner consultation 03/29/2011

CURRENT AND FUTURE LAND USE

Current Land Use (Check all that apply):

Crop Land: ☒ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☐ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): _____

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

Future Land Use (Check all that apply):

Crop Land: ☒ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☐ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): _____

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 330 Feet
Building Unit: 330 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 437 Feet
Above Ground Utility: 419 Feet
Railroad: 5280 Feet
Property Line: 350 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of nearest Well or edge of nearest Production Facility to nearest of each cultural feature as described in Rule 303.b.(3)A.
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☒ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit.
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 12/26/2013

SOIL

List all soil map units that occur within the proposed location. attach the National Resource Conservation Service (NRCS) report showing the "Map Unit Description" report listing the soil typical vertical profile. This data is to be used when segregating topsoil.

The required information can be obtained from the NRCS web site at <http://soildatamart.nrcs.usda.org/> or from the COGCC web site GIS Online map page found at <http://colorado.gov/cogcc>. Instructions are provided within the COGCC web site help section.

NRCS Map Unit Name: 42 - Nunn clay loam, 1 to 3 percent slopes

NRCS Map Unit Name: 82 - Wiley-Colby complex, 1 to 3 percent slopes

NRCS Map Unit Name: _____

PLANT COMMUNITY:

Complete this section only if any portion of the disturbed area of the location's current land use is on non-crop land.

Are noxious weeds present: Yes ☐ No ☐

Plant species from: ☐ NRCS or, ☐ field observation Date of observation: _____

List individual species: _____

Check all plant communities that exist in the disturbed area.

- ☐ Disturbed Grassland (Cactus, Yucca, Cheatgrass, Rye)
☐ Native Grassland (Bluestem, Grama, Wheatgrass, Buffalograss, Fescue, Oatgrass, Brome)
☐ Shrub Land (Mahogany, Oak, Sage, Serviceberry, Chokecherry)
☐ Plains Riparian (Cottonwood, Willow, Aspen, Maple, Poplar, Russian Olive, Tamarisk)
☐ Mountain Riparian (Cottonwood, Willow, Blue Spruce)
☐ Forest Land (Spruce, Fir, Ponderosa Pine, Lodgepole Pine, Juniper, Pinyon, Aspen)
☐ Wetlands Aquatic (Bullrush, Sedge, Cattail, Arrowhead)
☐ Alpine (above timberline)
☐ Other (describe): _____

WATER RESOURCES

Is this a sensitive area: ☐ No ☒ Yes

Distance to nearest

downgradient surface water feature: 245 Feet

water well: 4430 Feet

Estimated depth to ground water at Oil and Gas Location 8 Feet

Basis for depth to groundwater and sensitive area determination:

1) Closet permitted water well, Permit # 1026, is 4,430' north of the proposed location with a static water level of 8'. Closet surface water is a concrete ditch 245' east of proposed well site.

Is the location in a riparian area: ☒ No ☐ Yes

Was an Army Corps of Engineers Section 404 permit filed ☒ No ☐ Yes If yes attach permit.

Is the location within a Rule 317B Surface Water Supply Area buffer No zone:

If the location is within a Rule 317B Surface Water Supply Area buffer have all public water supply systems within 15 miles been notified: _____

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☒ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☒ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

1) Closet permitted water well, Permit # 1026, is 4,430' north of the proposed location with a static water level of 8'. Closet surface water is a concrete ditch 245' east of proposed well site.

2) A temporary completions area, operated by a 3rd party, approximately four acres will be utilized for up to 3 fresh water storage tanks to be used during completions operations. This area will be completely reclaimed. Please see attached map.

3) OGLA Pre-Application Notice attached.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.

Signed: _____ Date: 03/11/2014 Email: chris.mcrickard@encana.com

Print Name: Chris McRickard Title: Permitting Analyst

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Conditions Of Approval

All representations, stipulations and conditions of approval stated in this Form 2A for this location shall constitute representations, stipulations and conditions of approval for any and all subsequent operations on the location unless this Form 2A is modified by Sundry Notice, Form 4 or an Amended Form 2A.

COA Type

Description

--	--

Best Management Practices

No	BMP/COA Type	Description
1	General Housekeeping	Any material not in use that might constitute a fire hazard will be removed a minimum of twenty-five (25) feet from the wellhead, tanks and separator. Any electrical equipment installations inside the bermed area will comply with API RP 500 classifications and comply with the current national electrical code as adopted by the State of Colorado.
2	General Housekeeping	All surface trash, debris, scrap or discarded material connected with the operations of the property shall be removed from the premises or disposed of in a legal manner.
3	Material Handling and Spill Prevention	<ul style="list-style-type: none"> • Annual hydrostatic test on the oil dump line from the separator to the tank battery. • Annual hydrostatic “static” tests on our oil tanks. • Annual hydrostatic “static” tests on our produced water tank and water dump line from the separator to the produced water tank. • Lease Operator inspections of all equipment not to exceed 48 hours. • Monthly documented inspections (EU). • Annual environmental inspections of all battery and well equipment and pads. • Annual UT inspections of the pressure vessels and input into Encana's RIPL Predictive Integrity Maintenance Program. (HLP separators and fuel gas separators)
4	Material Handling and Spill Prevention	Well effluent containing more than ten (10) barrels per day of condensate or within two (2) hours after first encountering hydrocarbon gas of salable quality will be directed to a combination of sand traps, separators, surge vessels, and tanks as needed to ensure safe separation of sand, hydrocarbon liquids, water, and gas and to ensure salable products are efficiently recovered for sale or conserved and that non-salable products are disposed of in a safe and environmentally responsible manner.
5	Construction	The pad will be constructed in such a manner that noise mitigation may be installed and removed without disturbing the site or landscaping.
6	Construction	Subject pad will have all weather access roads to allow for operator and emergency response.
7	Construction	Encana utilizes 24” tall corrugated galvanized metal berm walls with a capacity in excess of 150% of the largest tank contained within the wall. In addition, Encana best practices mandates the use of impervious liners that extends under each storage tank and up the walls, permanently affixed to the top of the metal berm wall. Protrusions of piping that come through the liner include a fully sealed “boot” to prevent leakage.
8	Noise mitigation	Encana will perform a baseline noise survey prior to any operational activity measuring dBA at a distance 350 feet from the noise source (unless there is an occupied structure closer than that – then measurement will be taken 25 feet from the structure). If low frequency noise is a concern, measurement of dBC will be taken 25 feet from the occupied structure towards the noise source. As necessary, based on the survey, Encana will install temporary sound walls to minimize noise and light impacts during drilling and completions and will install permanent noise mitigation at the facility location as necessary to meet all COGCC regulations.
9	Noise mitigation	The subject location will be constructed to allow potential future noise mitigation installation without disturbance.
10	Drilling/Completion Operations	Guy line anchors in the DJ Basin are not installed. Encana will use an engineered base beam that we guy wire anchor the derricks to.
11	Drilling/Completion Operations	All newly installed or replaced crude oil and condensate storage tanks will be designed, constructed, and maintained in accordance with National Fire Protection Association (NFPA) Code 30 (2008 version). Encana will maintain written records verifying proper design, construction, and maintenance, and will make these records available for inspection by the Director. In addition, onsite inspections are conducted internally to insure guidelines are met.

Total: 11 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400540713	FORM 2A SUBMITTED
400548404	LOCATION PICTURES
400548405	LOCATION DRAWING
400548406	HYDROLOGY MAP
400548407	ACCESS ROAD MAP
400548408	NRCS MAP UNIT DESC
400548409	NRCS MAP UNIT DESC
400548410	MULTI-WELL PLAN
400548423	OTHER
400548424	WASTE MANAGEMENT PLAN
400569475	OTHER
400569487	SURFACE AGRMT/SURETY
400569912	EXCEPTION LOC REQUEST

Total Attach: 13 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Returned to draft: missing Certification of Compliance with Pre-Application Notice Rule 305.a.	3/12/2014 10:22:34 AM

Total: 1 comment(s)