

WELLBORE DIAGRAM

Directions: 18th St and Cherry St (Greeley) SE into

Bayswater E & P
Kuettel 14-10

SWSW Sec 10-T5N-R65W

SHL: 485' FSL, 860' FWL

BHL: 485' FSL, 860' FWL

Weld County CO

05-123-20146

Updated

11/15/2013

BCB

G.L.= 4642

K.B.= 4654

12

8-5/8" 24# set at 412'

Cmt'd w/ 340 sx to Surf.

TOC: 3020'

CBL

<-----222 jts of 2 3/8" J-55 ,4.7# EUE 8rd tbg meas-6993.18', SN@7004.58' KB

 \gg

»

CODL: 7022'-7032', 3 spf, 0.38" ehd

Frac on 08-01 w/ 98,658 gals Vistar 22 LHT Gel & 5,280# 100 Mesh, 225,920# 20/40 San

Re-perf 7022'-7032', 4 spf, 11/6/13

Re-Frac: on 11/8/2013 w/ 3,711 bbls Gel & 247,065 # 20/40 Sand

PBTD= 7,142'

4 1/2", 11.6# LTC 7191' (7-7/8" O.H.)

TD MD= 7,193'

Cmt'd w/ 455 sx