

FORM 5A

Rev 06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number: 400558656

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10261 4. Contact Name: JONATHAN RUNGE
 2. Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION Phone: (720) 420-5700
 3. Address: 730 17TH ST STE 610 Fax: (720) 420-5800
 City: DENVER State: CO Zip: 80202 Email: jrunge@iptengineers.com

5. API Number 05-123-29058-00 6. County: WELD
 7. Well Name: MATRIX Well Number: 11-29
 8. Location: QtrQtr: NWNW Section: 29 Township: 6N Range: 65W Meridian: 6
 9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: CODELL Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 10/22/2013 End Date: 10/22/2013 Date of First Production this formation: 11/05/2013

Perforations Top: 7212 Bottom: 7226 No. Holes: 56 Hole size: 042/100

Provide a brief summary of the formation treatment: _____ Open Hole:

Frac CODL w/ 352 bbls FR Pad, 121 bbls Linear Pad, 2554 bbls Crosslink Slurry (prop concentrations from 0.25-4.00# 20/40), Flush w/ 112 bbls FR

This formation is commingled with another formation: Yes No

Total fluid used in treatment (bbl): 3139 Max pressure during treatment (psi): 5282

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.34

Type of gas used in treatment: _____ Min frac gradient (psi/ft): 0.73

Total acid used in treatment (bbl): 0 Number of staged intervals: 1

Recycled water used in treatment (bbl): 0 Flowback volume recovered (bbl): 1255

Fresh water used in treatment (bbl): 3139 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 179005 Rule 805 green completion techniques were utilized:

Reason why green completion not utilized: _____

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 11/13/2013 Hours: 24 Bbl oil: 37 Mcf Gas: 51 Bbl H2O: 20

Calculated 24 hour rate: Bbl oil: 37 Mcf Gas: 51 Bbl H2O: 20 GOR: 1378

Test Method: FLOWING Casing PSI: 900 Tubing PSI: 350 Choke Size: 022/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1310 API Gravity Oil: 57

Tubing Size: 2 + 3/8 Tubing Setting Depth: 7196 Tbg setting date: 10/25/2013 Packer Depth: _____

Reason for Non-Production: _____

Date formation Abandoned: _____ Squeeze: Yes No If yes, number of sacks cmt _____

** Bridge Plug Depth: _____ ** Sacks cement on top: _____ ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JONATHAN RUNGE
Title: CONSULTANT Date: _____ Email jrunge@iptengineers.com
:

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400558700	WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)