

Noble Energy, INC
CORNISH # 1
05-123-10863

Proposed Wellbore Schematic

Re-enter and re-plug

KB elev - 4867'

GL elev - 4857'

Weld cap on 8 5/8" sur csg

8 5/8" sur csg set @ 504'
w/ 300 sks of cmt

Deepest Water well: 400'

Base Fox Hills 459'

250 sk cmt plug from 609' to surface

100 sk cmt plug set @ 3000'

NO PROD CSG
open hole to TD

50 sk cmt plug set @ 6500' (Nio @ 6538')

TD = 7405'