

CUNDALL 5-12
SWNW, Section 12-T1S-R68W
Adams County, CO
API No. 05-001-09492

Ground Elevation = 5,091'

KB Elevation = 5,107'

NOTE: Well is vertical well

Tubing Detail:

Jts	Desc	Length	Depth; ft
-----	------	--------	-----------

Need to obtain from field office

Rod Detail:

Jts	Desc	Length	Depth
-----	------	--------	-------

Need to obtain from field office

Treatment Desc:

7/1/2004 Frac Codell w/ 245,000# 20/40 sand and 3,150 bbls gelled water

Well Spud: 5/26/2004

← 12-1/4" Hole

Surface Casing:

8-5/8" 24#, set @ 1,131'
Cement w/ 610 sx

← TOC 3,870' from CBL

← 7-7/8" Hole

Production Casing:

4-1/2", 11.6# set @ 8,228' KB
Cement w/ 590 sx

Perf: Codell

7,938'-7,948' with 24 holes

PBTD @ 8,116' KB
TD @ 8,125' KB

Date: 3/17/2011
Change: Original
By: Jeff Rhodes