

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400574053

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 10447

4. Contact Name: Shauna DeMattee

2. Name of Operator: URSA OPERATING COMPANY LLC

Phone: (720) 508-8350

3. Address: 1050 17TH STREET #2400

Fax:

City: DENVER State: CO Zip: 80265

5. API Number 05-045-22095-00

6. County: GARFIELD

7. Well Name: BAT

Well Number: 12C-24-07-96

8. Location: QtrQtr: NESW Section: 24 Township: 7S Range: 96W Meridian: 6

Footage at surface: Distance: 1984 feet Direction: FSL Distance: 1924 feet Direction: FWL

As Drilled Latitude: As Drilled Longitude:

GPS Data:

Data of Measurement: PDOP Reading: GPS Instrument Operator's Name:

** If directional footage at Top of Prod. Zone Dist.: 2379 feet. Direction: FNL Dist.: 577 feet. Direction: FWL

Sec: 24 Twp: 7S Rng: 96W

** If directional footage at Bottom Hole Dist.: 2390 feet. Direction: FNL Dist.: 588 feet. Direction: FWL

Sec: 24 Twp: 7S Rng: 96W

9. Field Name: WILDCAT

10. Field Number: 99999

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 02/09/2014 13. Date TD: 02/15/2014 14. Date Casing Set or D&A: 02/18/2014

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 6165 TVD** 5676 17 Plug Back Total Depth MD 6103 TVD** 5614

18. Elevations GR 5183 KB 5198

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Mud, Pulsed Neutron, Triple Combo, and CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	20	16	75#	0	75	50	0	75	CALC
SURF	12+1/4	8+5/8	32#	0	1,874	535	0	1,900	CALC
1ST	7+7/8	4+1/2	11.6#	0	6,147	725	3,720	6,165	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	3,062		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	5,511		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	6,032		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

All casing and cement information are measured from KB. All formations are measured from surface. The As Drilled Plat and SHL lat/longs will be submitted with the final completion report.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Shauna DeMattee

Title: Permit Representative

Date: _____

Email: sdeattee@ursaresources.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400575034	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400574510	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400574054	Other	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
<u>Other Attachments</u>					
400574070	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400574071	LAS-PULSED NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400574073	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400574082	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)