

**AREA: N2**      **ROUTE: N24**   **Spud: 04/17/1971**      **WINS No.: 74282**      **AFE/WO#: 88421115**      **API#: 0512307303**

**Directions:** WCR 13 & WCR 32, E 1/8, N 1/4 INTO

HOLE SECTIONS			Size	Top	Btm TD Date			
SURFACE			12.25	12	563 04/17/1971			
PRODUCTION			7.88	563	7780 04/26/1971			
TUBULARS	Tool Type	Joints	Size	Weight	Grade	Thread	Top D	Bottom D
SURFACE CASING								
PRODUCTION CASING	Casing	13	8.63	24			12	563
	Casing	244	4.50	10.50	K-55	ST&C	12	7738
	Casing Float Collar	1	4.50				7738	7739
	Casing	1	4.50	11.60	K-55	ST&C	7739	7779
	Casing Guide Shoe	1	4.50				7779	7780
BRIDGE PLUG								
CAST IRON CEMENT RETAINER	CIBP With CMT Cap	1	4.50				7540	7542
	Cement Retainer	1	4.50				6981	6984
PRODUCTION TUBING								
BRIDGE PLUG	Tubing	208	2.38	4.70	J-55	External-Ups	12	6512
	Seating Nipple	1	2.38				6512	6513
	Notched Collar	1	2.38				6513	6513
BRIDGE PLUG								
BRIDGE PLUG	Cement Retainer	1	4.50				3824	3825
	Cast Iron Bridge Plu	1	8.63				100	102
CEMENT JOBS	Stage	Sacks	Cement Jobs			Top D	Btm D	cbl
SURFACE CASING								
	PRIM CMT 1ST STAGE	300	LEAD	50/50 POZ-MIX		12	400	No
	PRIM CMT 1ST STAGE	150	TAIL	G		400	563	No
PRODUCTION CASING								
	PRIM CMT 1ST STAGE	200		50/50 POZ-MIX		7116	7780	Yes
PRODUCTION CASING								
	SQUEEZE JOB	25	LEAD-2	NEAT		6302	6450	Yes
	SQUEEZE JOB	235	LEAD	50/50 POZ-MIX		6450	7090	Yes
--None--								
	ABANDONMENT PLUG	20	LEAD	FRESH WATER		6170	6540	No
--None--								
	ABANDONMENT PLUG	300	LEAD	FRESH WATER		3704	4700	No
--None--								
	ABANDONMENT PLUG	275	LEAD	FRESH WATER		410	1198	No
PERFORATIONS								
Formation	Zone	Top	Btm	Date	Reason	Comments		
SUSSEX		4700	4701	01/23/2014	CEMENT SQUEEZE			
		6450	6451	10/22/2013	CEMENT SQUEEZE	TOP SQUEEZE HOLES		
		7090	7091	10/22/2013	CEMENT SQUEEZE	BOTTOM SQUEEZE HOLES		
J SAND		7634	7664	06/18/1991	PRODUCTION	Under cmt capped CIBP & cmt ret		
J SAND		7638	7646	05/12/1971	PRODUCTION			
J SAND		7654	7660	05/12/1971	PRODUCTION			
Comments:								