

PDC Energy
Olson 14-29
SWSW 29 - 4N - 67W
Weld County, CO
Proposed Wellbore - NOT TO SCALE!!!
3/17/2014

API#: 05-123-20275

GL Elevation: 4999'

Surface Casing:
8 5/8" 24# @ 410' W/ 290 sks cmt.

First String
4 1/2" 10.5# @ 7512' w/ 175 sks cmt

Second String
0

Perforations	
Old:	Codell: 7348'-7358' (3 spf)
	0
	0
	0
New:	Codell: 7348'-7356' (3 spf)
	Niobrara B: 7132'-7140' (3 spf)
	Niobrara A: 7064'-7066' (2 spf)
	0

--

Top of Cement:
0'

--

Niobrara

Codell

PBTD:	7512'
Casing TD:	0

Notes

Annular fill cement to surface, RePerf/ReFrac Codell, Perf/Frac Niobrara