

Encana Natural Gas

Well : Billings 2G 18H
Field : Wattenberg
County : Weld County **State** : Colorado
Surface : Lat: 40.229230 Long: -105.054130
API # : 1297' FNL 275' FWL – S18 T3N R68W
Grd Elev : 5197' GL **KB Elevation**: 5227' KB

Prognosed Tops

3961' MD - Sussex
 4182' MD - Sussex Mrkr
 4421' MD - Shannon
 6191' MD - TP Buttes
 6990' MD - Sharon Springs
 7105' MD - Niobrara
 7286' MD - B Chalk

Well History:

Spud of Interval 3/27/14
 TD of Interval 3/28/14
 Sidetrack 4/3/14

9-5/8" 40# J55 LTC
 827' MD / 826' TVD
 Cmt'd w/ 367 sxs Class G

8.75" Open Hole

Tangent at 8 deg inclination

Top of Cement Plug at 3514' MD

Cmt Plug Details:

465 sxs 17.5# G Cmt
 Yield 0.94 cuft/sk
 Height of 800' at 30% XS

Bottom of Cement Plug at 4314' MD

Sidetrack KOP at 3600' MD

Top of fish at 4373' MD

Bottom of fish at 4408' MD

Fish Description:

8.75" PDC Bit
 6.5" Drilling Motor
 6.5" UBHO Sub
 35' in length

TD 7615' MD
 7063' TVD

Drawn by:

Gage Soehner

Date:

4/2/14