



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199762

Date <u>7-9-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>1-32 5x</u>	Lease <u>Felco</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700</u>	<u>(Xtreme #6)</u>		
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL	<u>920</u>
<u>Surface</u> <u>8 5/8" CSG-24"</u>	Bottom of Surface	FL	<u>910</u>
Plug	Plug Landed @ <u>866</u>	FL	Time On <u>1430</u>
Production	Pipe Landed @ <u>910</u>	FL	Plug Down <u>1730</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	<u>570</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete <u>1/4</u> # Per Sack <u>2052729026</u>				
Mileage Charge <u>80012090</u>	<u>186</u>	Miles		
Fuel Surcharge	<u>186</u>	Miles		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>1635</u>	<u>1641</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>1641</u>	<u>1706</u>	
Slurry Vol. <u>1.32³ Cu.Ft./Sk</u>	Change Valves	<u>1706</u>	<u>1709</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>1709</u>	<u>1730</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>68 °F</u>				
Total Slurry Vol. <u>134</u>	BBLs Cement			
Landed Plug @ <u>450</u>	PSI/Final Lift @ <u>200</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>55</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>62</u>			
<u>1217/1218</u>		Bulk Truck		<u>62/62</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Delia, Justin, Delia

Received By [Signature]

Customer or His Agent