

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400585477

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Eileen Roberts
Phone: (303) 2284330
Fax: (303) 2284286
Email: eroberts@nobleenergyinc.com

5. API Number 05-123-37193-00
6. County: WELD
7. Well Name: TREBOR
Well Number: B11-65-1HN
8. Location: QtrQtr: NWSW Section: 11 Township: 5N Range: 64W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 09/22/2013 End Date: 09/22/2013 Date of First Production this formation: 10/09/2013

Perforations Top: 7107 Bottom: 10484 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

Frac'd the Niobrara w/ 3257543 gals of PermStim and Slick Water with 4184960#'s of Ottawa sand.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 77560 Max pressure during treatment (psi): 5420

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.89

Total acid used in treatment (bbl): 0 Number of staged intervals: 18

Recycled water used in treatment (bbl): 4489 Flowback volume recovered (bbl): 467

Fresh water used in treatment (bbl): 73070 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 4184960 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 10/15/2013 Hours: 24 Bbl oil: 177 Mcf Gas: 278 Bbl H2O: 132

Calculated 24 hour rate: Bbl oil: 177 Mcf Gas: 278 Bbl H2O: 132 GOR: 1570

Test Method: FLOWING Casing PSI: 2163 Tubing PSI: 1511 Choke Size: 16/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1243 API Gravity Oil: 51

Tubing Size: 2 + 7/8 Tubing Setting Depth: 6836 Tbg setting date: 10/04/2013 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Eileen Roberts _____

Title: Regulatory Specialist _____

Date: _____

Email: eroberts@nobleenergyinc.com _____

:

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)