

**WPX ENERGY ROCKY MOUNTAIN, LLC**

**Federal NER 344-32**

**Rulison**

**SHL 189' FNL 2605' FWL (5 7S 93W) BHL 424' FSL 659' FEL (Section 32-T6S-R93W)**

**Section 5 T7S-R93W 6th PM**

**Garfield County Colorado**

**Formation Tops**

(Measured Depths)

"G" Sand @ 3798'  
Mesaverde @ 6466'  
Top of Gas @ 8196'  
Cameo @ 9410'  
Rollins @ 10,234'

PBTD @ 10,307'  
TMD @ 10,355'  
TVD @ 10,026'



Conductor 26" Hole 18" casing/liner 63' W/23.63 Sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9-5/8" 32.3 ppf Csg. Set @1158'  
In 13-1/2" Hole W/320 Sks. Cmt

Top Of Cement @ 5200'

Max Estimated Top Perf @ 7390'

4-1/2", 11.6 ppf. Csg. Set @10,343' W/1035 Sks Cmt