

WPX ENERGY ROCKY MOUNTAIN, LLC

Federal RU 21-5

Rulison

SHL 199' FNL 2597' FWL (5 7S 93W) BHL 192' FNL 2017' FWL (5 7S 93W)

Section 5 T7S-R93W 6th PM

Garfield County Colorado

Formation Tops

(Measured Depths)

"G" Sand @ 3619'

Mesaverde @ 6158'

Top of Gas @ 7890'

Cameo @ 9030'

Rollins @ 9872'

PBTD @ 9971'

TMD @ 10014'

TVD @ 9985'

Conductor 26" Hole 18" casing/liner 63' W/23.63 Sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9-5/8" 32.3 ppf Csg. Set @1162'

In 13-1/2" Hole W/320 Sks. Cmt

Top Of Cement @ 2939'

Max Estimated Top Perf @ 7047'

4-1/2", 11.6 ppf. Csg. Set @10,004' W/1350 Sks Cmt