

State #1

1590 FSL660 FWL NWSW 16 5N 61W 6th PM
Lat 40.39813 Long -104.22132 (from footages)
Weld County, Colorado
API #05-123-07701

Spud date 4/13/1973

4618 KB
4608 GL

10 sxs cement surface plug

8.625", 23#/ft Wt, Grade, 100', 12.25" hole
Cemented with 100 sxs + 3% CC

15 sxs cement shoe plug @ 100'

Water N/A
(Within 1 mile radius)

Completion Summary
Drilled to total depth of 6810' to test J-sand
Performed drill stem test on J-sand, low pressure
Filed to abandon 4/23/1973; dry hole
PB to bottom of surface casing

As found in well:
State #1

TOC N/A '

Niobrara 5944 '

Carlile 6243 '

D Sand 6635 '

J Sand 6700 '

7 7/8"

PBTD N/A ft
TD 6810 ft 4/22/1973

Updated 3/4/2014 jad