

US ROCKIES REGION

Anadarko Daily Summary Report

Well: DUTCHER ROY UNIT #2

Project: COLORADO-WELD-NAD83-UTM13

Site: DUTCHER ROY UNIT #2

Rig Name No: ENSIGN 350/350

Event: CONST- CAP WELL WORK

Start Date: 4/3/2014

End Date:

Spud Date: 9/9/1980

Active Datum: RKB @4,888.99usft (above Mean Sea Level)

UWI: 0/2/N/67/W/24/0/NWNE/6/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	04/03/2014		MIRU ENSIGN # 350 WP 200/200 PSI SP 0, SPOT IN PUMP AND TANK, BLOW WELL DOWN KILL WELL W/ 60 BBLS, ND WH NU BOPS, RU EMI SER, TOO H TALLY OUT 252 JTS, 40 GOOD JTS LD 212 BAD JTS RD EMI SDFN.
2	04/04/2014		RU WIERLINE RIH SET CIBP @ 7390' RD(WAITING FOR TBG,) TIH TALLY IN OF TRAILER TO 7330' CIRC GAS TEST CSG TO 1000 PSI, TOO H 90 JTS SDFN
3	04/05/2014		FINSH TOO H, RU WIERLINE RIH W/ CBL FROM 7360' TO SURFACE, RU 3-1/8 GUNS RIH SHOOT SQUEEZE HOLES @ 6880' / 6510' POOH RD WL, SDFN
4	04/07/2014		PU CICR TIH, SET @ 6560' BREAK CIRC, RU SANJEL PUMP 100 SX OF CEMENT RD, LD 6 JTS REVERSE CIRC, TOO H, DIGGING A HOLE ROUND SURFACE HEAD, SHUT DOWN CREW TRAVEL TO YARD.
5	04/08/2014		ND BOPS, ND WH & SUR H, INSTAL NEW SUR H WELDING 4-1/2 WELLED NIPPLE, INSTALL NEW 5000 PSI WH, NU BOP, TEST WH TO 1000 PSI , PU 3-7/8 ROCK BIT TIH TAG CEMENT @ 6480' DRILL OUT TO 6590' CIRC CLEAN LD 1 JT SDFN
6	04/09/2014		RU PS CONTINUE MILLING OUT CMT CIRC CLEAN RD PS TOO H, MIRU WIERLINE RIH \ CBL LOGG FROM 7150' TO 6300' POOH, PU 3-7/8 ROCK BIT, TAG @ 7207' LD 1 JT SDFN
7	04/10/2014		RU PS BREAK CIRC, MILLOUT CIBP, PUSHED DOWN TO 7946' RD PS, WET TBG SWABBING TOO H, RU TESTER PU NC XN TIH 41 JTS PACKER 207 JTS, SET PKR @ 6518 LAND @ 7820 W/ 248 JTS ND BOPS NU WH TEST PACKER TO 1000 PSI & WH TO 5000 PSI, SDFN.
8	04/11/2014		RU LUBRICADOR BROACH TBG TAG 6900' WORK BROACH TRUED TO XN @ 7820', POOH, RDMO.