

1625 Broadway
Suite 2000
Denver, CO 80202



Tel: 303.228.4000
Fax: 303.228.4280
www.nobleenergyinc.com

3/27/14

Colorado Oil and Gas Conservation Commission
The Chancery Building
1120 Lincoln Street, Suite 801
Denver, CO 80203
Attn: Mr. Matt Lepore, Director

RE: **Request to the Director for 318A.m. GWA Minimum Intrawell Distance Exception**
FIVE RIVERS K08-67-1HN
Niobrara New Drill
Township 4 North, Range 66 West, 6th P.M.
Section 9: SW/4NW/4: 2083' FNL & 512' FWL (Surface Location)
Weld County, Colorado

Dear Director:

Noble Energy Inc. (NEI) is planning to drill the above mentioned well to the Niobrara formation(s).

The lateral path of NEI's proposed horizontal well will be less than the 150' minimum distance from another well(s) as required by Rule 318A.m. (see well listed below). Please find attached a signed waiver from K P Kauffman. Please see Noble's Anti-Collision Mitigation BMP noted below.

RML 18-8

API No. 05-123-26543
Status: XX
24' from proposed location
Operator: K P Kauffman Company

Anti-collision:

Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5. During and Post stimulation: Noble Energy Inc. will comply with the COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated 5/29/12.

Noble respectfully requests that the COGCC review the enclosed information and approve the requested exception location Application for Permit to Drill the captioned well.

Respectfully,

Susan Miller
Regulatory Analyst III