

## US ROCKIES REGION

**Anadarko Daily Summary Report**

Well: STREAR 13-10

Project:COLORADO-WELD-NAD83-UTM13

Site:STREAR 13-10

Rig Name No:CONCORD 3/3

Event: ABANDONMENT

Start Date: 2/21/2014

End Date: 4/14/2014

Spud Date: 7/15/2005

Active Datum: RKB @5,001.99usft (above Mean Sea Level)

UWI: 0/2/N/67/W/10/0/SWSW/6/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	02/21/2014		MIRU, ND frac valve NU BOP's SWI SDFN.
2	02/22/2014		PU Retrieving head Tally in 228 jts, circulated sand & release RBP. TOOHD LD RBP. Trip back in hole W/ retrieving head + 228 jts SWI SDFN.
3	02/24/2014		Circulated sand off & release RBP TOOHD. RU WL RIH set CIBP @ 7240, PU NC SN TIH to 7235. RU sanjel pump 30 sks of thermal 35 LD 22 jts load the hole W/ drilling mud, PUH to 5100 RU sanjel pump 65 sks class G 13.2, bbls PUH to 3985 pump drilling mud SDFN.
4	02/25/2014		TIH Tag TOC @ 4150 TOOHD, RU WL RIH cut csg @ 1240. Circulated well W/ drilling mud & ND BOP's unland csg TOOHD, TIH to 1348, RU Sanjel Pump 220 sks 57 bbls, TOOHD Drained EQP SDFN
5	02/26/2014		TIH tag TOC @ 471 LD tag jts, RU WL RIH set 8.625 CIBP @ 100 ft. PT CIBP to 1000 psi test ok ND BOP's. RDMO
6	04/14/2014		Crew travel, safety. Dug up surface casing. Cut surface casing 6' below GL. Tagged @ 100'. Filled casing w 47 bags 5000# cement. Capped casing w metal plate containing well info. Backfilled.
7	04/14/2014		TIME : 19:00, ROUTE : HZ2, WINS: 74471, PROJECT TYPE: P&A, PROD: NB/CD, BATT#: 34002703, GATHERER: KMG, STATION: 45388, LINE : UNKNOWN, COMMENTS: P&A'd OFFLINE.