

STATE OF
COLORADO

<jay.krabacher@state.co.us>

Re: NER 434-32 - CBL Deferment Request

1 message

Krabacher - DNR, Jay <jay.krabacher@state.co.us>

Fri, Apr 25, 2014 at 1:59 PM

To: "Haddock, Reed" <Reed.Haddock@wpenergy.com>

Cc: "Andrews - DNR, David" <david.andrews@state.co.us>, "Porraz, Isac" <Isac.Porraz@wpenergy.com>

Reed (Isac):

Looks good. COGCC concurs with the CBL deferment request for this well.

Jay Krabacher



On Fri, Apr 25, 2014 at 10:02 AM, Haddock, Reed <Reed.Haddock@wpenergy.com> wrote:

Jay, Dave:

WPX Energy Rocky Mountain, LLC is requesting a CBL deferment on the Federal NER 434-32 located in the Section 5, T7S-R93W. Attached is a temperature survey that was performed after cementing the 4 ½" production casing on the subject well.

Information pertaining to the request is as follows:

Well:	Federal NER 434-32
API:	05-045-21778-00
Location:	Section 5 T7S-R93W
Surface Csg:	9 5/8" set and cemented at 1170'
Production Csg Cement Date:	4 ½" @ 10,108' – cemented 4/20/14
Cement:	1050 sks
Cement top from survey:	3550' Estimated
Estimated top of gas:	7383' Estimated
Estimated Top Perf:	7384' Estimated
Temp Survey:	4/21/14 Attached
Volume to fill annular:	Hole remained full following cementing operations

Please let me know if you need additional information to approve this deferment. After deferment is received,

WPX Energy will continue to monitor the bradenhead pressure until the CBL has been performed and notify if pressure exceeds 150 psig.

04/20/2014	15:30	6 HR	0 BBL	0 PSI
04/20/2014	21:30	12 HR	0 BBL	0 PSI
04/21/2014	09:30	24 HR	0 BBL	0 PSI
04/22/2014	09:30	48 HR	0 BBL	0 PSI
04/23/2014	09:30	72 HR	0 BBL	0 PSI



Reed Haddock

Regulatory Specialist Staff

WPXENERGY

303-606-4086 (Office)

720-544-3267 (Cell)

Reed.Haddock@WPXEnergy.com

Jay Krabacher

N W Area Engineer

co_dnr_div_ogcc_300_rgb_ltrhd_v3



P 970.625.2497 x4

C 970.589.6180