

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400564919

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

03/05/2014

Well Name: DOLPH

Well Number: 15C-1HZ

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: Cheryl Light

Phone: (720)929-6461

Fax: (720)929-7461

Email: cheryl.light@anadarko.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: NENW Sec: 1 Twp: 2N Rng: 66W Meridian: 6

Latitude: 40.173375

Longitude: -104.727031

Footage at Surface: 470 feet FNL/FSL FNL 2225 feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 5013

County: WELD

GPS Data:

Date of Measurement: 10/29/2013 PDOP Reading: 1.8 Instrument Operator's Name: BART PFEIFER

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL
597 FNL 1936 FWL 460 FSL 1638 FEL
Sec: 1 Twp: 2N Rng: 66W Sec: 1 Twp: 2N Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 2 North, Range 66 West, 6th P.M.

Section 1: Lot 2 (N/2NW/4) (79.24), S/2NW/4, S/2

Section 3: Lot 2 (N/2NW/4) (78.95), S/2NW/4, S/2

Section 11: NW/4, S/2

Section 13: NW/4, S/2

Section 15: NW/4, S/2

Section 23: NW/4, S/2

Section 25: NW/4, S/2

Township 2 North, Range 65 West, 6th P.M.

Section 5: Lot 2 (N/2NW/4) (71.79), S/2NW/4, S/2

Section 7: Lots 1 and 2 (W/2W/2) (151.48), E/2W/2, SE/4

Section 9: NW/4, S/2

Section 19: Lots 1 and 2 (W/2W/2) (143.56), E/2W/2, SE/4

Section 29: NW/4, S/2

Containing 5725.20 acres, more or less

Weld County, Colorado

Total Acres in Described Lease: 5725 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 781 Feet

Building Unit: 1050 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 3125 Feet

Above Ground Utility: 2396 Feet

Railroad: 5280 Feet

Property Line: 420 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit

- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.

- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 245 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

UNIT CONFIGURATION:
2N-66W SEC 1: E/2NW/4, W/2NE/4, NW/4SE/4, NE/4SW/4, S/2SE/4

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		320	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 12409 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 17 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☐ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Other

Other Disposal Description:

Please see Comments section. Disposal description will not fit in space provided.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	1375	520	1375	0
1ST	8+3/4	7	26	0	7826	830	7826	0
1ST LINER	6+1/8	4+1/2	11.6	6732	12409			

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

☒ Rule 318A.a. Exception Location (GWA Windows).

☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

OTHER DISPOSAL DESCRIPTION:

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent at which point they will either be land applied or taken to a licensed, commercial disposal site; decided upon based off of laboratory analysis of fluids. Cuttings disposal: Water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field depending on what is feasible at time of drilling.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 336495

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Ronett Powers

Title: Regulatory Analyst II Date: 3/5/2014 Email: djregulatory@anadarko.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 4/27/2014

Expiration Date: 04/26/2016

API NUMBER

05 123 39332 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.
--	---

Best Management Practices

No BMP/COA Type

Description

1	Planning	The nearest building unit is located 1050' away from this oil and gas location, therefore it is not within a Designated Setback Location and is exempt from 604.c.
2	Drilling/Completion Operations	Kerr McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
3	Drilling/Completion Operations	<p>Prior to drilling operations, Operator may perform an anti-collision review of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision review may include MWD or gyro surveys and surface locations of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well may only be drilled if the anti-collision review results indicate that the risk of collision is sufficiently low as defined by the anti-collision plan, with separation factors greater than 1.5, or if the risk of collision has been mitigated through other means including shutting in wells, plugging wells, increased drilling fluid in the event of lost returns or as is appropriate for the specific situation. In the event of an increased risk of collision, that risk will be mitigated to prevent harm to people, the environment or property. For the proposed well, upon conclusion of drilling operations, an as-constructed directional survey will be submitted to COGCC with the Form 5.</p> <p>Please see the attached 318A.m letter for a list of well(s) identified by the operator as being within 150 feet of the proposed well(s). If no letter is attached, the operator has not identified any wells as being within 150 feet of the proposed well(s) at the time of permitting.</p>

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
2114593	ANTI-COLLISION WAIVER
2482641	SURFACE CASING CHECK
400564919	FORM 2 SUBMITTED
400565252	WELL LOCATION PLAT
400565253	PROPOSED SPACING UNIT
400565255	EXCEPTION LOC REQUEST
400565258	EXCEPTION LOC WAIVERS
400565262	DIRECTIONAL DATA
400565265	DEVIATED DRILLING PLAN
400565268	SURFACE AGRMT/SURETY
400565270	OPEN HOLE LOGGING EXCEPTION
400565759	OffsetWellEvaluations Data

Total Attach: 12 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Received 318A.m waiver. Ready to pass.	4/11/2014 8:23:15 AM
Permit	Corrected distance to nearest lease line to 0. Confirmed by opr. Rule 317.o exception granted. See attached Open Hole Logging Exception request letter. Current wells on pad are within 150' non-lateral portion of wellbore. Corrected nearest well penetrating the formation to 17'. Requested 318A.m waiver.	3/25/2014 8:53:32 AM
Permit	This form passes completeness.	3/6/2014 11:14:47 AM

Total: 3 comment(s)