

US ROCKIES REGION

Anadarko Daily Summary Report

Well: PSC 14-13

Project:COLORADO-WELD-NAD83-UTM13

Site:PSC 14-13

Rig Name No:BASIC 1549/1549

Event: CONST- CAP WELL WORK

Start Date: 4/17/2014

End Date:

Spud Date: 7/25/1992

Active Datum: RKB @4,905.99usft (above Mean Sea Level)

UWI: SW/SW/0/3/N/68/W/13/0/0/6/0/S/0/W/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	04/17/2014		MIRU Basic 1549.
2	04/21/2014		ND wekk head & frac valve. Unland csg. NU BOP. PU 1 1/4" tbg to 1040'. Wait on cementers. RU Sanjel. Brk circ. Pump 250 sks Type III cmt w/.25 #/sk Polyflake. LD 1 1/4" tbg. Land csg. NU tbg head & BOP. SI. SDFN.
3	04/22/2014		RU Warrior. Run CBL from 1200' to surface. Cmt from 1050' to 100'. PU retrieving head & TIH. Circ sand off RBP & release. TOO. TIH & release 2nd RBP. TOO. PU NC/XN nipple & TIH. Tag fill @ 7730'. Land w/243 tjs tbg @ 7646'. ND NU Test WH to 5000# OK RD