

Noble Energy, INC
Motis # 1
05-123-05732

Proposed Wellbore Schematic

Re-enter and re-plug
KB elev - 4675'
GL elev - 4665'

Weld cap on 9 5/8" sur csg

9 5/8" 25.6# sur csg set @ 214'
w/ 200 sks of cmt

Base Fox Hills: 497'

Deepest Water well: 680'

329 sk cmt plug set from surface to 830'

100 sk cmt plug set @ 3000'

? size prod csg backed-off @ 5500' (7 7/8" OH to surface)

CIBP set @ 6000'

UNKNOWN size prod csg set from 5500'-6000'
w/ 150 sks of cmt

TD = 6334'