

Noble Energy, INC
Motis # 1
05-123-10878

Current Wellbore Schematic

Status - DA
KB elev - 4680'
GL elev - 4670'

10 sk cmt plug from surface to 30'

8 5/8" 24# sur csg set @ 98'
w/ 60 sks of cmt

15 sk cmt plug from 85'-115'
(1/2 in sur csg and 1/2 outside sur csg)

Base Fox Hills 509'

Deepest Water well: 680'

NO PROD CSG
7 7/8" open hole to TD

TD = 6347'

OH filled with 10 ppg mud from 115'-6347'