

Noble Energy, INC  
Motis # 1  
05-123-10878

### Proposed Wellbore Schematic

Re-enter and re-plug

KB elev - 4680'

GL elev - 4670'

Weld cap on 8 5/8" sur csg

8 5/8" 24# sur csg set @ 98'  
w/ 60 sks of cmt

Base Fox Hills 509'

Deepest Water well: 680'

307 sk cmt plug from surface to 830'

50 sk cmt plug set @ 3000'

50 sk cmt plug set @ 5300'

NO PROD CSG  
7 7/8" open hole to TD

TD = 6347'