

US ROCKIES REGION

Anadarko Daily Summary Report

Well: HSR-SEKICH FARMS 9-18

Project: COLORADO-WELD-NAD83-UTM13

Site: HSR-SEKICH FARMS 9-18

Rig Name No: CONCORD 3/3

Event: ABANDONMENT

Start Date: 3/21/2014

End Date: 5/1/2014

Spud Date: 2/27/1994

Active Datum: RKB @4,834.99usft (above Mean Sea Level)

UWI: 0/3/N/67/W/18/0/SENE/6/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	03/21/2014		MIRU, BLEW DOWN KILLED IT, ND WH NU BOP, TALLY OUT 227 JTS 1 1/4, RU WL RIH W/ GAUGE. PU CIBP RIH SET IT @ 6900, PU SN TIH W/ TBG TO TOP CIBP, RU SANJEL PUMP 20 SKS OF THERMAL 35, PUH CIRCULATED CLEAN W/ DRILLING MUD, SWI SDFN.
2	03/22/2014		TOOH W/ 1 1/4 TBG, RU WL RIH CUT CSG @ 4422. TRIED TO CIRCULATED DID NOT CIRCULATE ND BOP's UNLAND CSG NU UP, TOOH & TRIP BACK IN CIRCULATED DOWN TO 4422. RU SANJEL PUMP 300 SKS OF 0-1-0-G, LD 34 JTS ROLL THE HOLE W/ DRILLING MUD, SWI SDFN.
3	03/24/2014		TAG TOD @ 3580 PUH TO 880, RU SANJEL PUMP 190 SKS TYPE 3. RU WL RIH TAG TOC @ 220 SET 8 5/8 CIBP @ 94 FT, PT CIBP TO 1000 PSI TEST OK NU BOP's, ROMO.
4	05/01/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 65'. Filled casing stub with 28 bags 5000# cement. Capped casing with metal plate containing well info. Backfilled.
5	05/01/2014		TIME : 17:30, ROUTE : N21, WINS: 74162, PROJECT TYPE: P&A, PROD: NB/CD, BATT#: 34003299, GATHERER: DCP, STATION: 232760, LINE : UNKNOWN, COMMENTS: P&A'd OFFLINE.