

US ROCKIES REGION			
Anadarko Daily Summary Report			
Well: HEIN WILLARD GU #1			
Project: COLORADO-WELD-NAD83-UTM13		Site: HEIN WILLARD GU #1	
Event: ABANDONMENT		Rig Name No: LEED 724/724	
Start Date: 2/10/2014		End Date:	
Active Datum: RKB @4,995.99usft (above Mean Sea Level)		Spud Date: 1/17/1973	
UWI: 0/1/N/67/W/4/0/NESW/6/0/0/0/0/0/0			
Report No	Report Date	MD (usft)	24 Hr Summary
1	03/28/2014		MIRU Leed 724. Kill well. TOO H & tally tbgs. RU Warrior. Run 3.81" gauge ring. Set CIBP @ 8000'. Had miss run on 1st setting. Dump bail 2 sks cmt on CIBP. SI. SDFN.
2	03/29/2014		RU Warrior. Run CBL from 7970' to surface. Cmt above Nio- 7320'. Cmt from 2100' to 1640'. Cmt from 890' to 224'. Shoot squeeze holes @ 7290' & 6920'. Set retainer @ 6930'. PU stinger & TIH. Hydrotest tbgs to 6000 psi while TIH. SI. SDFN.
3	03/31/2014		RU Sanjel. Squeeze from 7290' to 6920' w/130 sks 50/50 pozmix w/20% silica flour. TOO H. RU Warrior. Shoot squeeze holes @ 4900' & 4290'. Set retainer @ 4300'. PU stinger & TIH. RU Sanjel. Pump 20 bbls SMS. Pump 410 sks G cmt (See Remarks)
4	04/01/2014		RU Warrior. Shoot squeeze holes 1435' & 875'. Set retainer @ 885'. PU stinger & TIH. RU Sanjel. Squeeze Fox Hills from 1435' to 240'. LD tbgs to 240' & circ cmt to tank. TOO H. RU Warrior & cut off csg @ 210'. Circ well. ND. Unland csg. NU. LD csg. SI. SDFN
5	04/02/2014		TIH w/tbgs to 240'. RU Sanjel. Spot 40 sks Type III cmt from 240' to 96'. Circulated cmt. LD tbgs to 93'. Circ cmt from well. LD tbgs. ND BOP. RU Warrior. Tag cmt top @ 96'. Set 8 5/8" CIBP @ 80'. NU BOP. Test CIBP to 1000 psi. OK. ND BOP. RDMO.
6	05/06/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 74'. Filled casing w 38 bags 5000# cement. Capped casing with metal plate containing well info. Backfilled.

REMARKS:

03/31/14 - w/.25 #/sk Ployflake. TOO H. SI. SDFN.