

FORM
5A
Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



| | | | |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

Document Number:
400599069

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

| | |
|---|--|
| 1. OGCC Operator Number: <u>47120</u> | 4. Contact Name: <u>Katie Kistner</u> |
| 2. Name of Operator: <u>KERR MCGEE OIL & GAS ONSHORE LP</u> | Phone: <u>(720) 9294317</u> |
| 3. Address: <u>P O BOX 173779</u> | Fax: _____ |
| City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80217-</u> | Email: <u>katie.kistner@anadarko.com</u> |

| | |
|---|------------------------------|
| 5. API Number <u>05-123-38548-00</u> | 6. County: <u>WELD</u> |
| 7. Well Name: <u>PARAGON</u> | Well Number: <u>10N-31HZ</u> |
| 8. Location: QtrQtr: <u>SWSE</u> Section: <u>6</u> Township: <u>1N</u> Range: <u>65W</u> Meridian: <u>6</u> | |
| 9. Field Name: <u>WATTENBERG</u> | Field Code: <u>90750</u> |

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION
Treatment Date: 04/06/2014 End Date: 04/11/2014 Date of First Production this formation: 04/25/2014
Perforations Top: 7607 Bottom: 14353 No. Holes: 0 Hole size: 0
Provide a brief summary of the formation treatment: Open Hole:

COMPLETED THROUGH AN OPEN HOLE LINER FROM 7607-14353.
136326 BBL CROSSLINK GEL, 6171 BBL LINEAR GEL, 47663 BBL SLICKWATER, 190160 BBL TOTAL FLUID.
630213# 40/70 GENOA/SAND HILLS SAND, 13261415# 40/70 OTTAWA/ST. PETERS SAND, 13891628# TOTAL SAND.

This formation is commingled with another formation: Yes No
Total fluid used in treatment (bbl): 190160 Max pressure during treatment (psi): 7526
Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.30
Type of gas used in treatment: _____ Min frac gradient (psi/ft): 0.86
Total acid used in treatment (bbl): 0 Number of staged intervals: 40
Recycled water used in treatment (bbl): 0 Flowback volume recovered (bbl): 8799
Fresh water used in treatment (bbl): 190160 Disposition method for flowback: DISPOSAL
Total proppant used (lbs): 1389162 Rule 805 green completion techniques were utilized:
Reason why green completion not utilized: _____

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/01/2014 Hours: 24 Bbl oil: 142 Mcf Gas: 290 Bbl H2O: 60
Calculated 24 hour rate: Bbl oil: 142 Mcf Gas: 290 Bbl H2O: 60 GOR: 2042
Test Method: FLOWING Casing PSI: 1300 Tubing PSI: _____ Choke Size: 14/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1205 API Gravity Oil: 48
Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____

Reason for Non-Production: _____

Date formation Abandoned: _____ Squeeze: Yes No If yes, number of sacks cmt _____

** Bridge Plug Depth: _____ ** Sacks cement on top: _____ ** Wireline and Cement Job Summary must be attached.

Comment: _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.
Signed: _____ Print Name: Katie Kistner
Title: Regulatory Analyst Date: _____ Email: rscdjpostdrill@anadarko.com

Attachment Check List

| Att Doc Num | Name |
|-------------|------|
| | |

Total Attach: 0 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|-------------------|----------------|---------------------|
| | | |

Total: 0 comment(s)